STELLENBOSCH
STELLENBOSCH • PNIEL • FRANSCHHOEK
MUNISIPALITEIT • UMASIPALA • MUNICIPALITY

Application Number: TP1070/2025 – LU/17383
Our File Reference Number: Farm 742/5, Paarl Division
Your Reference Number: None
Enquiries: Ulrich von Molendorff
Contact No: 021 – 808 8682
Email address: Ulrich.Vonmolendorff@stellenbosch.gov.za

PER E-MAIL: [redacted]

Sir / Madam

APPLICATION FOR PERMISSION REQUIRED IN TERMS OF A CONDITION OF APPROVAL: FARM 742/5, PAARL DIVISION

1. The above application refers.

2. The duly authorised decision maker has decided on the above application as follows:

   2.1 That the following application(s) in terms of Section 15(2)(1) of the Stellenbosch Municipal Land Use Planning Bylaw for a permission in terms of a condition of approval on Farm 742/5, Klapmuts, namely:

   2.1.1 Precinct Plan for Precinct 2, as per Condition 3.4 of the Land Use approval letter dated 25 August 2023.

   2.1.2 Landscaping Plan for Precinct 2, as per Condition 3.9 of the Land Use approval letter dated 25 August 2023.

   2.1.3 Architectural Guidelines applicable to Precinct 2, as per Condition 3.8 of the Land Use approval letter dated 25 August 2023.

   2.1.4 Site Development Plan for portion 4 (erf 10) a portion within the Precinct 2, as per Condition 3.5 of the Land Use approval letter dated 25 August 2023.

BE APPROVED in terms of Section 60 of the said Bylaw and subject to co.

3. The approval is subject to the following **conditions** imposed in terms of Section 66 of the said Bylaw.

3.1 The approval only applies to the applications under consideration and shall not be construed as authority to depart from any other legal prescriptions or requirements from Council or other legislation or Bylaws or Regulations that may be applicable.

3.2 Development charges are payable in accordance with the prevailing and applicable Council Tariffs at the time of payment prior to the transfer of the first property or approval of any building plans, whichever occurs first, or as may be agreed on in writing with the Director Infrastructure Services.

3.3 A service agreement regarding the responsibilities for the provision of engineering services be entered into with the Municipality prior to the construction of any Engineering services or infrastructure in terms of Section 66(3) and Section 82(4) of the said Bylaw, which service agreement includes and complies with the conditions as imposed by the Directorate Infrastructure Services in their letter with reference Civil LU 2774 and dated 4 November 2024 and attached as ***Annexure E***.

3.4 The Development of Precinct 2 be implemented in accordance with The Precinct 2 Plans, Drawing No Klapmuts / P2-2025, Dated Feb 2025 Pages 1 to 6, Attached as **Annexure A**.

3.5 The development of Precinct 2 be implemented in accordance with the Architectural Design Guidelines (Development Manual / 2020, Dated: 03/2023) for the Light Industrial Precinct of the Bridge, in so far as it is applicable to the approval granted for Precinct 2. Architectural Design Guidelines, attached as ***Annexure B.***

3.6 The Landscaping Plan for Precinct 2 be implemented in accordance with the Stellenbosch Bridge Landscaping Master Plan, Drawn By: CNDV, Drawing No: 2997-03-MP-Rev 02, Dated: 25 Feb 2025, attached as ***Annexure C.***

3.7 The Development of Portion 4 / Erf 10 a portion of Precinct 2 be implemented in accordance with Site Development Plan for ERF 10 (PORTION 4), Drawing No: Portion 4-01-2025, Pages 1-5 Dated: 21/11/2024 & Landscaping Plan Drawing No: 2996-03-LP-Rev 03, Dated: 10 May 2024, attached as ***Annexure D.***

3.8 A street naming and numbering plan, be approved by the Stellenbosch Municipality prior to issuing of a section 28 certificate.

3.9 Building plans must be submitted and approved by the Municipality prior to the commencing of any building work, including the preparation of land, which will only be approved when all relevant (or qualified) conditions of approval have been complied with.

3.10 The approval granted shall not exempt the applicant from complying with any other legal prescriptions or requirements that might have a bearing on the proposed use.

4. **The reasons for the above decision are as follows:**

4.1 The Precinct Plan, Precinct Landscaping Plan and Site Development Plan for erf 10 a portion within the Precinct is compliant with the approval granted for the subject property in terms of the basket of rights.

4.2 The plan for approval will only facilitate the implementation of the land use approval and not grant any additional land use rights.

4.3 The Architectural Design Guidelines applicable to the Light Industrial Precincts: Dated 03/2023 have taken the visual impact assessment into consideration as the height and the scale of the buildings are restricted.

4.4 The plan for approval promotes the smart city philosophy of the development as it has taken the recommendations of the visual impact assessment into consideration.

5. You are hereby informed in terms of section 79(2) of the Stellenbosch Municipal Land Use Planning Bylaw of your right to appeal the above decision to the Appeal Authority within 21 days from the date of notification of the above decision. Please note that no late appeals or an extension of time for the submission of appeals are permitted in terms of Section 80(1)(a) of the said By-Law.

6. Appeals must be submitted by completing the required form with the prescribed information to satisfy the requirements of Section 80(2) of the said By-law, failing which the appeal will be invalid in terms of Section 81(1)(b) of the said By-Law.

7. **Appeals must be addressed to the Municipal Manager and submitted to his/ her designated official by means of e-mail at the following address: landuse.appeals@stellenbosch.gov.za**

8. Any party (applicant or other) who lodges an appeal must pay the applicable appeal fee in terms of the approved municipal tariffs and submit the proof of payment together with the

appeal. The **LU** Reference number on this correspondence, or the applicable Erf/ Farm Number must be used as the reference for the payment of the appeal fee.

9. The appeal form and approved tariff structure and the banking details for the General Account can be accessed and viewed on the municipal website. For any enquiries the office can be contacted at landuse.appeals@stellenbosch.gov.za or 021 – 808 8684.

10. An applicant who lodges an appeal must also adhere to the following requirements stipulated in terms of section 80(3) to (7) of the said By-law:
    (a) Simultaneously serve the appeal on any person who commented on the application concerned and any other person as the municipality may determine.
    (b) The notice by the applicant must invite persons to comment on the appeal within 21 days from date of notification of the appeal.
    (c) The notice must be served in accordance with section 35 of the said legislation and in accordance with the prescripts or such additional requirements as may be determined by the Municipality.
    (d) Proof of serving the notification must be submitted to the Municipality at the above E-mail address within 14 days of serving the notification.

11. Kindly note that no appeal right exists in terms of Section 62 of the Local Government Municipal Systems Act, No 32 of 2000.

12. Kindly note the above decision in the case of any approval, is suspended, and may therefore not be acted on, until such time as the period for lodging appeals has lapsed, any appeal has been finalised, and you've been advised accordingly.

Yours faithfully

FOR DIRECTOR PLANNING AND ECONOMIC DEVELOPMENT

DATE: 11/3/2025

STELLENBOSCH
STELLENBOSCH • PNIEL • FRANSCHHOEK

MUNICIPALITY • UMASIPALA • MUNISIPALITEIT

ANNEXURE A



DEVELOPMENT DATA - SITE 4

LAND USE:	INDUSTRIAL
ERF SITE AREA:	15 932m²
TOTAL COUNCIL GLA:	6807 m²
FAR:	0.5

PARKING DATA

PROVIDED PARKING: 69

PARKING REQUIREMENTS

1 bays / 100m² GLA:
6807m² GLA = 68 bays required

TOTAL REQUIRED BAYS: 68 bays

LEGEND

- PROPOSED 16M ACCESS SERVITUDE.
- PROPOSED 10M MUNICIPAL SEWER SERVITUDE.
- PROPOSED 3,5M MUNICIPAL WATER SERVITUDE.
- PROPOSED 5M PRIVATE SERVICES SERVITUDE.
- BULK WATER.
- BULK STORMWATER
- SEWER

PRECINCT PLAN
SCALE: 1 : 9000

mbx
Argitekte

General notes:
1. All work is to be done in accordance with the National building Regulations.
2. All materials and workmanship are to comply with the relevant SA.BUS. codes and/or the specified educational codes where applicable in the Architectural specifications. Where no South African Standard Specification exists, British Standards, ISO codes of South African Approved Standards shall be followed. Drawings and the recommendations and requirements of such documents to be considered a minimum standard for the works.
3. The contractor shall in all aspects of the work comply with the provisions of the Occupational Health and Safety Act, 1993 (Act No 85 of 1993) and any regulations promulgated in terms of that Act or the Factories Machinery and Building Works Act of 1941.
4. The contractor shall set up, document and maintain a quality assurance and quality control system, in accordance with SANS 9001/ISO 9001, with respect to the construction work. The Architect, shall have the right to inspect the system at whatever time he deems fit to ensure the requirements of the Specification. Should the Contractor or any of his sub-contractors be certified to the SANS 9000 family of standards then similar checks would accordingly.
5. This drawing must be read in conjunction with all the relevant drawings, schedules and specifications from MBX and all other consultants referred to the project.
6. All portions of the works related to any service or consultant's information is to be done in accordance with the National Building Regulations.
7. Figured dimensions only is not to be scaled. Figured dimensions to be used. All dimensions are in millimeters unless otherwise stated.
8. All dimensions and levels must be checked on site by the contractor before putting work in hand.
9. All work to be executed by competent persons qualified for the specific trade.
10. This drawings is copyright reserved and remains the property of Iskander Bezuidenhout (Pty) Ltd

CLIENT

ARCHITECT

CLIENT
STELLENBOSCH
BRIDGE PROPERTIES
(PTY) LTD

Project Address
STELLENBOSCH BRIDGE
Town/City
KLAPMUTS / P2-2025
Drawing Name
PRECINCT PLAN

STELLENBOSCH
BRIDGE
PRECINCT 2
Date: 25 Feb 2025

drgnr	Drawing Nr	revision
01	9001	

Pg 1 – 6

C:\Users\Admin\Desktop\Projects\STELLENBOSCH BRIDGE\PRECINCT PLANS\STELLENBOSCH BRIDGE PRECINCT PLANS.rvt 2025/02/25 05:32:14

mbx
Argitekte

General Notes:
1. All work is to be done in accordance with the National Building Regulations.
2. All materials and workmanship are to comply with the relevant S.A.B.S. codes and or the specified international codes where applicable in the « Architectural specifications. Where relevant South African National Standards, British Standards, BS codes of practice, or Agrément Certificates applicable to the design exist, the recommendations and requirements of such documents to be considered a minimum standard for the works.
3. The contractor shall in all aspects of the works comply with the provisions of the Occupational Health and Safety Act, 1993 (Act No 85 of 1993) and any regulations promulgated in terms of that Act or the Factories Machinery and Building Works Act of 1941.
4. The contractor shall set up, document and maintain a quality assurance and quality control system, in accordance with SANS 9001/ISO 9001, able to be checked to the satisfaction of the Architect, that all materials and workmanship, whatever their sources, meet the requirements of the Specification. Should the Contractor or any of his sub-contractors be certified to the SANS 9000 family of standards then evidence there of to be submitted.
5. This drawing must be read in conjunction with all the relevant drawings, schedules and specifications from MBX and all other consultants related to the project.
6. All portions of the works related to any service or consultant 's information is to be done in accordance with the National Building Regulations.
7. This drawing is not to be scaled. Figured dimensions to be used. All dimensions are in millimeters unless otherwise stated.
8. All dimensions and levels must be checked on site by the contractor before putting work in hand.
9. All work to be executed by competent persons qualified for the specific trade.
10. This drawings is copyright reserved and remains the property of Mventer Bouwe Kompanie (Pty) Ltd

REV	DATE	DRAWN	DESCRIPTION



LEGEND

- BULK WATER.
- BULK STORMWATER
- SEWER

PRECINCT INFO PLAN
SCALE: 1 : 1000

CLIENT

ARCHITECT

CLIENT
STELLENBOSCH BRIDGE PROPERTIES (PTY) LTD

Project Address
STELLENBOSCH BRIDGE
Town/City
KLAPMUTS IPZ-2025
Drawing Name
PRECINCT INFORMATION PACK

STELLENBOSCH BRIDGE

PSZ-6

Stage	Drawing number	Revision
01	9000	

C:\Users\mvcontract.mbx\ADSMITH POWER WAREHOUSE STELLENBOSCH BRIDGE\ADSMITH POWER WAREHOUSE STELLENBOSCH BRIDGE_R25_CENTRAL_MODEL.RVT 2025 10:22:17



PRECINCT PLAN PERIMITER WALLS

SCALE: 1 : 1000

mbx
Argitekte

General Notes:
1. All work is to be done in accordance with the National building Regulations.
2. All materials and workmanship are to comply with the relevant S.A.B.S. codes and or the specified international codes where applicable in the - Architectural specifications. Where relevant South African National Standards, British Standards, BS codes of practice, or Agrément Certificates applicable to the design entails, the recommendations and requirements of each documents to be considered a minimum standard for the works.
3. The contractor shall in all aspects of the works comply with the provisions of the Occupational Health and Safety Act, 1993 (Act No 85 of 1993) and any regulations promulgated in terms of that Act or the Factories Machinery and Building Works Act of 1941.
4. The contractor shall set up, document and maintain a quality assurance and quality control system, in accordance with SANS 9001/ISO 9001, safe to be checked to the satisfaction of the Architect, that all materials and workmanship, whatever their sources, meet the requirements of the Specification. Should the Contractor or any of his sub-contractors be certified to the SANS 9000 family of standards then monitor these works accordingly.
5. This drawing must be read in conjunction with all the relevant drawings, schedules and specifications from MBX and all other consultants related to the project.
6. All portions of the works related to any service or consultant 's infrastructure is to be done in accordance with the National Building Regulations.
7. This drawing is not to be scaled, Figured dimensions to be used. All dimensions are in millimeters unless otherwise stated.
8. All dimensions and levels must be checked on site by the contractor before putting work in hand.
9. All work to be executed by competent persons qualified for the specific trade.
10. This drawings is copyright reserved and remains the property of Meester Bosmans Kompanjie (Pty) Ltd

REV	DATE	DRAWN	DESCRIPTION

CLIENT

ARCHITECT

CLIENT
STELLENBOSCH BRIDGE PROPERTIES (PTY) LTD

Project Address
STELLENBOSCH BRIDGE
Town/City
KLAPMUTS / P2-2025
Drawing Name
PRECINCT BOUNDARY PLAN

STELLENBOSCH BRIDGE

P5 3-6

stage	drawing series	revision
01	9002	

C:\Users\Environment Users - MKSMITH POWER WAREHOUSE STELLENBOSCH-BRBOKSKA-SMITH POWER WAREHOUSE STELLENBOSCH-BRBOKSKA-SMITH POWER-CENTRAL_MODEL_REVIT.rvt
MODELS\KSKA-SMITH POWER-CENTRAL_MODEL_REVIT.rvt

2025/05/05 19:23:19

PROPOSED STREET LIGHT PLAN

SCALE: 1 : 1000

mbk
Argitekte

General Notes:
1. All work is to be done in accordance with the National Building Regulations.
2. All materials and workmanship are to comply with the relevant S.A.B.S. codes and or the specified international codes where applicable in the - Architectural specifications. Where relevant South African National Standards, British Standards, SS codes of practice, or Agrément Certificates applicable to the design exists, the recommendations and requirements of such documents to be considered a minimum standard for the works.
3. The contractor shall in all respects of the works comply with the provisions of the Occupational Health and Safety Act, 1993 (Act No 85 of 1993) and any regulations promulgated in terms of that Act or the Factories Machinery and Building Works Act of 1941.
4. The contractor shall set up, document and maintain a quality assurance and quality control system, in accordance with SANS 9001:ISO 2001, who is to be checked to the satisfaction of the Architect, that all materials and workmanship, whatever their sources, meet the requirements of the Specification. Should the Contractor or any of his sub-contractors be certified to the SANS 9000 family of standards then monitor these works accordingly.
5. This drawing must be read in conjunction with all the relevant drawings, schedules and specifications from MBK and all other consultants related to the project.
6. All portions of the works related to any service or consultants' information is to be done in accordance with the National Building Regulations.
7. This drawing is not to be scaled, figured dimensions to be used. All dimensions are in millimeters unless otherwise stated.
8. All dimensions and levels must be checked on site by the contractor before putting work in hand.
9. All work to be executed by competent persons qualified for the specific trade.
10. This drawings is copyright reserved and remains the property of Meester Bouers Kumpanje (Pty) Ltd

REV	DATE	DRAW	DESCRIPTION

CLIENT

ARCHITECT

CLIENT
STELLENBOSCH BRIDGE PROPERTIES (PTY) LTD

Project Address
STELLENBOSCH BRIDGE
Town/City
KLAPMUTS / P2-2025
Drawing Name
Street lighting

STELLENBOSCH BRIDGE

Pg 4-6

Page	Drawing number	Revision
01	9005	

C:\Users\Johan Swart\Desktop_WORK IN PROGRESS_MBK\STELLENBOSCH BRIDGE\STELLENBOSCH BRIDGE\STELLENBOSCH BRIDGE_SMITH POWER WAREHOUSE.rvt
2025/05/26 10:22:40

SUMMARY TABLE **Table No 1** **01-Jun-24**

The Bridge - Stellenbosch: Development Rights

Precinct	ALLOCATED RIGHTS					UTILISED RIGHTS					REMAINING RIGHTS				
	Resi (units)	Business (FA – m²)	Industrial (FA – m²)	Institut (FA – m²)	Total (m²) Non Res Floor Area	Resi (units)	Business (Fa – m²)	Industrial (FA – m²)	Institut (FA – m²)	Total (m²) Non Res Floor Area	Resi (units)	Business (FA – m²)	Industrial (FA – m²)	Institut (FA – m²)	Total (m²) Non Res Floor Area
Precinct 1A	**0**	**10 000**	**0**	**0**	**10 000**	**0**	**0**	**0**	**0**	**0**	**0**	**10 000**	**0**	**0**	**10 000**
Precinct 1B	**150**	**50 000**	**0**	**10 000**	**60 000**	**0**	**0**	**0**	**0**	**0**	**150**	**50 000**	**0**	**10000**	**60 000**
Precinct 1C	**150**	**23 800**	**0**	**10 000**	**33 800**	**0**	**0**	**0**	**0**	**0**	**150**	**23 800**	**0**	**10000**	**33 800**
Precinct 2	**0**	**20 000**	**40 000**	**0**	**60 000**	**0**	**0**	**7003**	**0**	**7003**	**0**	**20 000**	**32 997**	**0**	**52 997**
Precinct 3A	**0**	**6 900**	**17 400**	**0**	**24 300**	**0**	**0**	**0**	**0**	**0**	**0**	**6 900**	**17 400**	**0**	**24 300**
Precinct 3B	**0**	1 500	16 000	0	**17 500**	**0**	**0**	**0**	**0**	**0**	**0**	**1 500**	**16 000**	**0**	**17 500**
Precinct 3C	**0**	5 100	43 600	0	**48 700**	**0**	**0**	**0**	**0**	**0**	**0**	**5 100**	**43 600**	**0**	**48 700**
Precinct 4A	**300**	0	0	0	**0**	**0**	**0**	**0**	**0**	**0**	**300**	**0**	**0**	**0**	**0**
Precinct 4B	**800**	0	0	0	**0**	**0**	**0**	**0**	**0**	**0**	**800**	**0**	**0**	**0**	**0**
Precinct 4C	**500**	0	0	0	**0**	**0**	**0**	**0**	**0**	**0**	**500**	**0**	**0**	**0**	**0**
Precinct 5	**0**	8 000	0	0	**8 000**	**0**	**0**	**0**	**0**	**0**	**0**	**8 000**	**0**	**0**	**8 000**
Precinct 6A	**100**	29 000	0	0	**29 000**	**0**	**0**	**0**	**0**	**0**	**100**	**29 000**	**0**	**0**	**29 000**
Precinct 6B	**200**	28 700	0	0	**28 700**	**0**	**0**	**0**	**0**	**0**	**200**	**28 700**	**0**	**0**	**28 700**
Totals	**2 200**	183 000	117 000	20 000	**320 000**	**0**	0	7 003	0	**7 003**	**2 200**	183 000	109 997	20 000	**312 997**

Note: Application Precinct shown in **RED**

THE BRIDGE, STELLENBOSCH - BULK TABLE

TABLE NO: 1

01 June 2024

The Bridge, Stellenbosch : Development Rights

Precinct	Erf No	Project Name	Zoning	Area (m²)	Erf Size (m²)	ALLOCATED RIGHTS					UTILISED RIGHTS					REMAINING RIGHTS				
						Residential (units)	Business (floor area – m²)	Industrial (floor area – m²)	Institutional (floor area – m²)	Total (m²) Non Res Floor Area	Residential (units)	Business (floor area – m²)	Industrial (floor area – m²)	Institutional (floor area – m²)	Total (m²) Non Res Floor Area	Residential (units)	Business (floor area – m²)	Industrial (floor area – m²)	Institutional (floor area – m²)	Total (m²) Non Res Floor Area
Precinct 1A	8		Mixed-use	90 200		**0**	**10 000**	**0**	**0**	**10 000**	**0**	**0**	**0**	**0**	**0**	**0**	**10 000**	**0**	**0**	**10 000**
	47											0								
Precinct 1B	8		Mixed-use	110 390		**150**	**50 000**	**0**	**10 000**	**60 000**	**0**	**0**	**0**	**0**	**0**	**150**	**50 000**	**0**	**10000**	**60 000**
	42										0	0		0						
	43										0	0		0						
	44										0	0		0						
	45										0	0		0						
	46										0	0		0						
Precinct 1C	8		Mixed-use	64 000		**150**	**23 800**	**0**	**10 000**	**33 800**	**0**	**0**	**0**	**0**	**0**	**150**	**23 800**	**0**	**10000**	**33 800**
	38										0	0		0						
	39										0	0		0						
Precinct 2	3		Industrial	123 300		**0**	**20 000**	**40 000**	**0**	**60 000**	**0**	**0**	**7003**	**0**	**7003**	**0**	**20 000**	**32997**	**0**	**52 997**
	28											0	0							
	29											0	0							
	30	Smith & Power	Industrial		13 932							0	7003							
Precinct 3A	5		Industrial	58 300		**0**	**6 900**	**17 400**	**0**	**24 300**	**0**	**0**	**0**	**0**	**0**	**0**	**6 900**	**17400**	**0**	**24 300**
	21											0	0							
Precinct 3B	6		Industrial	38 500		**0**	1 500	16 000	0	**17 500**	**0**	**0**	**0**	**0**	**0**	**0**	**1 500**	**16000**	**0**	**17 500**
												0	0							
Precinct 3C	7		Industrial	88 600		**0**	5 100	43 600	0	**48 700**	**0**	**0**	**0**	**0**	**0**	**0**	**5 100**	**43600**	**0**	**48 700**
	26											0	0							
	27											0	0							
Precinct 4A	50		Residential	59 400		**300**	0	0	0	**0**	**0**	**0**	**0**	**0**	**0**	**300**	**0**	**0**	**0**	**0**
											0									
Precinct 4B	51		Residential	106 000		**800**	0	0	0	**0**	**0**	**0**	**0**	**0**	**0**	**800**	**0**	**0**	**0**	**0**
											0									
Precinct 4C	51		Residential	111 300		**500**	0	0	0	**0**	**0**	**0**	**0**	**0**	**0**	**500**	**0**	**0**	**0**	**0**
Precinct 5	10		Mixed-use	58 100		**0**	8 000	0	0	**8 000**	**0**	**0**	**0**	**0**	**0**	**0**	**8 000**	**0**	**0**	**8 000**
												0								
Precinct 6A	35		Mixed-use	63 600		**100**	29 000	0	0	**29 000**	**0**	**0**	**0**	**0**	**0**	**100**	**29 000**	**0**	**0**	**29 000**
											0	0								
Precinct 6B	36		Mixed-use	93 400		**200**	28 700	0	0	**28 700**	**0**	**0**	**0**	**0**	**0**	**200**	**28 700**	**0**	**0**	**28 700**
											0	0								
Totals				**1 065 090**		**2 200**	183 000	117 000	20 000	**320 000**	**0**	0	7 003	0	**7 003**	**2 200**	183 000	109 997	20 000	**312 997**

Note: Application Erf highlighted in RED

STELLENBOSCH

AntonLotz

STELLENBOSCH
STELLENBOSCH • PNIEL • FRANSCHHOEK

MUNICIPALITY • UMASIPALA • MUNISIPALITEIT

ANNEXURE B

DRAFT
03 / 2023

STELLENBOSCH
BRIDGE | BHULORHO | BRUG

ANNEXURE C
LIGHT INDUSTRIAL PRECINCTS

DEVELOPMENT MANUAL | 2020



CONTENTS

SECTION 1 - INTRODUCTION

SECTION 2 - URBAN DESIGN PRINCIPLES

2.1 Stellenbosch Bridge Masterplan
2.2 Building Heights
2.3 Indicative Plans for Light Industrial Precincts
2.4 Access and Movement
2.5 Sections and Proposed Edge Conditions

SECTION 3 - ARCHITECTURAL CODES AND GUIDELINES FOR (PRECINCTS 1 AND 2 SOUTH)

3.1 Urban Design Elements
3.2 Architectural Style and Elements
3.3 Materials and quality of work
3.4 Colours and textures
3.5 Feature Elements Colour Palette
3.6 Architectural codes: elements of the building
3.7 General Design Guidelines and Restrictions
3.8 Street and Public Space Elements

SECTION 4 - ARCHITECTURAL CODES AND GUIDELINES FOR (PRECINCT 1 NORTH)

4.1 Urban Design Elements
4.2 Materials and quality of work
4.3 Colours and textures
4.4 Feature Elements Colour Palette
4.5 Architectural codes: elements of the building
4.6 General Design Guidelines and Restrictions
4.7 Street and Public Space Elements

ANNEXURES

ANNEXURE E: TABLE SUMMARISING MATERIAL USE FOR EACH BUILDING ELEMENT

References

Image Reference 01 (Ref 01)
Stellenbosch Agri- Park - https://www.findawarehouse.co.za/results/new-development/commercial/stellenbosch stellenbosch-outskirts/15/ (Web Ref IND15)

Image Reference 02 (Ref 02)
Val de Vie Estate, Stellenbosch

SECTION 1

INTRODUCTION

This design manual manages the development of the architectural and environmental identity of the Stellenbosch Bridge Precinct. It has been prepared by the developers and their professional team and aims to establish, maintain and control the architectural character and unique architectural identity of Stellenbosch Bridge, without inhibiting the individual's creativity and style.

The elements that form the essence of the Stellenbosch Bridge architectural character and the control of these elements are explained in this document. These control elements are, amongst other things; the covering, overhangs, pitch, colour and articulation of the roofs; all exterior paint colours; the street and environmental interfaces; the appearances and proportions of the window and door openings penetrating wall surfaces and the relationships between buildings. Pictures within this document are suggestive and for clarity, to avoid misinterpretations and to ensure consistency of Architectural elements within the precinct.

By controlling these elements, the full potential of Stellenbosch Bridge will be realized, thus growing the investment that developers will make in their individual properties.

The continued updating of the Architectural Design Manual is necessary to ensure that new properties at Stellenbosch Bridge are developed to maintain the overall Stellenbosch Bridge aesthetic and architectural character. Any amendments within this document supersede previous issues.

NOTE: No decision or waiver which the Developers Assessment Panel or Controlling Architect may approve shall be construed as creating a precedent for future decisions. Strict adherence to the guidelines will be observed. The Developer's Assessment Panel reserves the right to strictly enforce adherence to the guidelines.

The Stellenbosch Bridge Developer's Assessment Panel and the Aesthetic Committee will ensure that the guidelines are complied with during, both design and construction phases of each building project.

Stellenbosch Bridge is aiming for a 5* Greenstar precinct rating, and all buildings are to achieve a minimum 4* Greenstar rating as per the Green Building Council of South Africa (GBCSA) requirements. All buildings in the Stellenbosch Bridge Development need to conform to the Green Star Guidelines. Refer to the Green Building Council of South Africa (GBCSA) Green Star Guidelines in Annexure H. For further information refer to the Green Building Council of South Africa (GBCSA) website: www.gbcsa.org.za.

CONTROL

The control is through the Stellenbosch Bridge Developer's Assessment Panel and its appointed consultants. The control will be effected by: applying the general restrictions; following a mechanism for plan approvals; applying a code of conduct and rules for construction activities and monitoring construction work on site.

Stellenbosch Bridge:
Lorne Dawson : lorne@stb-bridge.co.za

Controlling Architect:
Osmond Lange Architects
Graham Wilson : grahamw@o-l.co.za
Francois Nortje : francoisn@o-l.co.za
Trisha Naik: trishan@o-l.co.za

Building Control Officer:

Controlling Landscape Architects:
Square One Landscape Architects
Julia McLachlan : julia@sq1.co.za

The following architectural guidelines deals with the Light Industrial Precincts within the Stellenbosch Bridge Development which includes:

- **Light Industrial:** data centers/ commercial/ manufacturing/ warehousing & distribution/ utility service / parking.

The Light Industrial Precincts are located on the eastern and northern perimeters on the development.

This manual must be read in conjunction with the Stellenbosch Bridge Development Manual.

PERMISSIBLE HEIGHTS FOR LIGHT INDUSTRIAL PRECINCTS:

INDUSTRIAL ZONE	STOREYS
All buildings	2-3

Stellenbosch Bridge Masterplan - Light Industrial Precincts

SECTION 2 - MASTERPLAN



2.2 PROPOSED BUILDING HEIGHTS

BUILDING HEIGHTS

- 5 STORIES ABOVE STREET LEVEL
- 4 STORIES ABOVE STREET LEVEL
- 3 STORIES ABOVE STREET LEVEL
- 2-3 STORIES ABOVE STREET LEVEL

2.3. INDICATIVE MASTERPLAN FOR LIGHT INDUSTRIAL PRECINCT 1



2.3. INDICATIVE MASTERPLAN FOR LIGHT INDUSTRIAL PRECINCT 2



2.4. ACCESS AND MOVEMENT



Light Industrial Precinct. Portion 2 of Farm 744 - Access Points

2.4. ACCESS AND MOVEMENT

LEGEND

- DEDICATED CYCLE PATH
- CYCLIST USES STREET
- PEDESTRIAN NETWORK

2.5. EDGE CONDITION: LOCATIONS OF INTERFACE OF INDUSTRIAL BUILDINGS ACROSS THE STELLENBOSCH BRIDGE BOULEVARD



SECTION 1: INTERFACE OF INDUSTRIAL AREA WITH EXISTING KLAPMUTS RESIDENTIAL AREA - STREET CONDITION





SECTION 2: INTERFACE OF INDUSTRIAL BUILDINGS ACROSS THE STELLENBOSCH BRIDGE BOULEVARD



SECTION 3: INTERFACE OF INDUSTRIAL AREA WITH EXISTING KLAPMUTS RESIDENTIAL AREA - STREET CONDITION





EDGE CONDITION 4: INTERFACE OF INDUSTRIAL AREA WITH EXISTING KLAPMUTS RESIDENTIAL AREA - HOUSING CONDITION



SECTION 5: NEW ACCESS ROAD



SECTION 6: LIGHT INDUSTRIAL AREA 2 IN RELATION TO THE N1 HIGHWAY





SECTION 7: SECTION THROUGH INDUSTRIAL PRECINCT 2 - SOUTHERN PRECINCT





ARCHITECTURAL CODES AND GUIDELINES FOR INDUSTRIAL PRECINCTS

KEY:

- PRECINCTS 1 AND 2 SOUTH
- PRECINCT 2 NORTH



Stellenbosch Bridge Masterplan - Light Industrial Precincts

SECTION 3 - ARCHITECTURAL CODES AND GUIDELINES FOR INDUSTRIAL PRECINCTS 1 AND 2 SOUTH.

(SEE SEPERATE CODES AND GUIDELINES FOR PRECINCT 2 NORTH)

3.1. URBAN DESIGN ELEMENTS

3.1.1 BUILT FORM AND SCALE

The industrial buildings are conceptualized as having two components, a street-facing office block defining the entrance and public facade, and an industrial structure, positioned in such a manner as to accommodate a turning circle for delivery vehicles and surface parking, as indicated in the adjacent images.

3.1.1.1. Site consolidations will be favorably considered, especially for irregular stands that will be more usable if consolidated.

3.1.1.2 Industrial erven that are in close proximity to the Mixed Use Precinct should respond to the Office Park design guidelines, in addition to the particular Industrial design guidelines.

3.1.1.3 HEIGHT OF BUILDINGS

Maximum Height at Apex	18m
Maximum height at Eaves	12m

Office portions of the buildings to be a maximum of two storeys high

(Subject to planning approval)



Example of Typical Industrial Site



Plan of Typical Industrial Site

3.1.2 SOLID TO VOID RATIO

The solid to void ratio is recommended to set a common trend for the ratio of mass, void and material use on the office façade.

The proposed solid to void ratio on the office façade is:

- 60-70% Solid: Plaster, concrete, cladding systems or combinations thereof.
- 30-40% Void: Glazing, louvered elements, clear openings / recessed courtyards or combinations thereof.
- 0-10% Accent colour/elements: Any colour or distinctive elements / combinations thereof.

3.1.3 FACADE

- Residential architectural elements should be avoided. The architecture of large-scale light industrial buildings is appropriate and encouraged.

- The facade towards the dominant external roads and railways should be of a corporate character. The warehouse component of the building that is visible from the road should be treated as a commercial façade.

- The scale and proportion of the facades and their relationship towards the streets needs to be considered. The scale of the facades should be appropriately broken down and articulated. Breaking and articulating the facade into thirds of the length may be used as a guide. The proportions of the façade design should determine the appropriateness of the breaks.

- The façade of the building along the external roads is expected to cover a substantial portion of the site width. Façade extensions concealing side yards may form part of the façade.

3.1.4 BUILDING ENVELOPE

- The office and warehouse components of the building should be designed in good proportional relation.

- Minimum pitched warehouse structures are encouraged.

- Roofs should be addressed as part of the building envelope design.

3.1.5 PLINTHS

- Plastered brick, face brick and concrete plinths are to be designed in good proportion to the envelope.

3.1.6 LEGIBILITY

- Buildings on prominent corners and intersections have to be enhanced in form and material to emphasize and utilize the prominent position.

- Signage and way-finding must be clear but sophisticated and presented for approval to the Developer's Assessment Pane with the stage 02 submission drawings

3.2. ARCHITECTURAL STYLE AND ELEMENTS

The main purpose of these guidelines is to control the architectural and environmental identity of Stellenbosch Bridge in order to establish a timeless and collective architectural identity.

The intention is to adopt and use the elements derived from regional Cape architecture in conjunction with a contemporary approach, which includes focus on proportions, simplicity, scale, massing, traditional plan form, vertical proportions, human scale, detailing and colours in a unique and cohesive manner to achieve an attractive homogeneous architectural language.

Scale and proportion are crucial in the establishment of a cohesive architectural language. Careful consideration should therefore be given to the articulation of the building forms, their roofs, wall openings and detailing in order to achieve an attractive homogeneous architectural language.

Focal features such as fountains, traditional Cape chimneys, low walls, pergolas, verandas in conjunction with indigenous planting and trees to mention just a few, will enhance and complement the character and promote a qualitative development known for its charm, beauty and ultimately its own unique "sense of place".

It is believed that flexibility of interpretation is important to encourage variety within the constraints of these guidelines.

In order to achieve the above objectives, the following elements are addressed:

3.3. Materials and Quality of Work
3.4. Colours and Textures
3.5 Feature Elements Colour Palette
3.6. Architectural Codes: Elements of the Building.
3.7. General Design Guidelines and Restrictions.
3.8. Street and Public Space Elements

Indicative Look and Feel Images for Industrial Precinct

3.3. MATERIALS AND QUALITY OF WORK

3.3.1 Building materials of a high quality are to be used in order to ensure the structural integrity of the buildings over time, and to maintain their appearance.

3.3.2 Within the constraints of the colour code a wide range of materials is possible.

3.3.3 In general, materials which are high quality and low maintenance and which assist in the expression of the architecture should be used.

3.3.4 All materials and their application are to be to the satisfaction of the Developer's Assessment Panel whose judgment will be directed by, but not limited to, the extent to which any material is integral to achieving a high quality, architectural design.

3.3.5 All materials should have an adequate record of application in the local climatic conditions.

3.3.6 High quality materials such as suitably treated glass, anodised or coated aluminum, stainless steel, and natural stone are acceptable and encouraged. Other high quality products will be considered but only at the discretion of the Developer's Assessment Panel.

3.3.7 All surface coatings are to be long lasting, enduring in quality and appearance with low to moderate maintenance needs.

3.3.8 Wall materials may vary from high quality masonry block to sealed or painted textured plaster surface, suitable stone and offshutter concrete.

3.3.9 The choice of materials should reflect energy conservation consciousness, appropriate to the building's use.

3.3.10 All buildings should have articulated façades with the use of shading devices, and generous overhangs strongly encouraged.

3.3.11 The latest issues of specifications, regulations and codes of practice (e.g. SABS/SANS specifications) shall be applicable. Wherever the SABS/SANS has prepared specifications for materials or products, such materials or products, are to be made and supplied to the Bureau's specification, and further, where materials and products are manufactured by Permit Holders of the SABS, such materials and products must be supplied with the SABS/SANS Codes of Practice.

3.4 COLOURS AND TEXTURES

3.4.1 A range of white; dark greys, natural stone; and timber should be used as a unifying theme of all architecture throughout the Industrial area.

3.4.2 THE FOLLOWING WALL FINISHES ARE PERMITTED:

(i) Smooth plaster and paint. (colour to the approved palette)

(ii) A limited extent of fairface brickwork as a feature element, to the extent specifically approved by the committee, with paint finish. (colour to approved palette).

(iii) Integral coloured rendered wall coatings such as Marmoran, Gama Zenith and Earthcote. (colour to the approved palette)

(iv) Smooth off shutter. (Class 1) concrete, unpainted)

(v) Designers are encouraged to use the wall finishes in combinations.

3.4.3 LIST OF SUGGESTED / PREFERRED COLOURS & TEXTURES:

(i) General - white to grey, sand to taupe, monochromatic as shown.

(ii) A single field colour and accent colour may be chosen from the following approved colour palette.

The approved palettes are: (Plascon or equal paint colours)

- FIELD
  - AW: Arniston White;
  - AW: Arniston White 50% LT;
  - CAS 1, WHITE.
- ACCENT
  - B5-E1-3 Gravel Road;
  - B5-E2-2 Grimsby;
  - B5-E2-3 Whisper.

Note that the location and extent of any accent colour must be marked on the submission drawings for approval.

3.5 FEATURE ELEMENTS COLOUR PALETTE

ROOFS, DOORS, WINDOW SHUTTERS & FRAMES, BALUSTRADES & OTHER

The colours of feature elements are limited to the monochrome palette.

Certain feature elements of different colours or materials might be approved by the panel, on a discretionary basis.

By keeping the roof colours and feature element colours in the same monochrome tones, it gives the estate a uniform appearance and contemporary style.

Alternative accent colours may be permissible subject to approval by the Developer's Assessment Panel .



Images showing the muted colour palette and range of textures for SBP.

3.6. ARCHITECTURAL CODES: ELEMENTS OF THE BUILDING

3.6.1 FAÇADE TREATMENT: HORIZONTAL TREATMENT & VERTICAL MODULATION

(i) The design of the façade must add to the continuity of the street edge and the cohesiveness of the entire precinct.

(ii) The manner in which the building meets the ground must be addressed positively: a plinth or base is suggested.

(iii) As with other elements of the composition, the onus is on the architect to demonstrate to the Developer how any of the above elements are to relate to adjacent buildings, existing or not, and promote continuity of streetscape.

(iv) The scale and placement of the buildings is important in providing a unity of structure. Extensive, unrelieved façades are discouraged, as are isolated and standalone ones.

(v) The proportioning system and façade composition used is a vital element in the overall design of the building and the manner in which it is to be used. The architect will be expected to demonstrate to the Developer's Assessment Panel how the module relates to the overall design of the building.

(vi) All apertures and fenestration should be carefully considered in a proportional system that brings all windows, doors, balconies and recesses into a relationship with the façade's specific modulation.

3.6.2 FAÇADE MATERIALS AND COLOURS

The facade treatment should follow the general guidelines for materials and colours, as specified for Stellenbosch bridge.

3.6.3 SHADING DEVICES

(i) Buildings are required to be energy efficient and must include passive solutions to climate control to reduce reliance on mechanical solutions.
Such approaches include facade layering, shading of glass, suitable shading of north, east and west facades.

(ii) Most sun-screening devices such as balconies, colonnades, canopies, awnings, eaves, overhangs and multi-planar façades are encouraged.

(iii) Where heat-retardant glass is to be used, and subject to the materials specification in Annexure E, reflective mirror-faced glazing is not permitted.

Images showing articulated facades, with visually permeable fronts, with recesses and overhangs

3.6.4 ROOFING

(i) A varying roofscape made up of pitched and 'flat' roofs is envisaged.
Permitted materials include:

- **High quality seamless fix, factory colour coated roof sheeting**
- **Concrete trafficable roof** with appropriate finish, drainage, insulation and waterproofing
- **'Green Roof'** – consisting of appropriate planting on fill on a Concrete roof with appropriate drainage, insulation and waterproofing.

(ii) The roof should be considered as an integral aesthetic component of the building. The architecture must consider the relationship of the building to the skyline and to adjacent developments when viewed from various perspectives.

(iii) All roof pitches should not to exceed 40°.

(iv) Gable walls may project above the roof surface as parapets or may terminate at the roof surface in which case the roof covering must be carried over the head of the wall to form a verge (barge board).

(v) The top of the gable end walls must consist of straight and simple lines and may not have rounded elements. It is recommended that these elements be kept simple and without any elaborate decoration, however plain/simple plaster copings over the top of these walls are permissible; and the line of the gable wall must always follow the pitch of the roof line except where flat roofs has been used.

(vi) Roofs must have clipped or flush eaves on the longitudinal side of the building.

(vii) Roofs may not project on the gable end side.

(viii) Any equipment required at roof level must be suitably concealed and may not be exposed to the exterior and must be approved by the Developer's Assessment Panel. No satellite dishes, TV aerials and radio antennas allowed.

(ix) Provision must be made by owners for a network connection. A full guideline pertaining to network connections can be found in the Technical Guidelines.

(ix) Long spanned roofs must favor a north-south orientation.

(x) All roofs to be a dark monochrome colour from the Feature Elements colour palette in this Manual. Garage & carport roofs must match the material & colour of the main structures.

THE FOLLOWING MATERIALS MAY BE UTILISED:
- Any profile metal sheeting. Colours to match Feature Elements palette. It must conform to the contemporary feel of the estate.
- Visible translucent sheeting should be clearly marked on the drawings.

THE FOLLOWING MATERIALS MAY NOT BE UTILISED:
- Tiles are not allowed

MATERIALS & COLOURS FOR FLAT ROOFS
- Flat concrete roofs can be planted or covered with loose stone.
- Fascias, barge boards to match roof or wall colours.
- Gutters to match roof colours or wall colours.
- Eaves without gutters are allowed if building is provided with apron.
- No PVC gutters or downpipes to be used.

Images illustrating the roof as an integral part of the building aesthetic.

3.6.4.1 SUSTAINABLE ROOFS

Sustainable roofing zones are defined as "areas of a roof assembly where a solar photovoltaic electricity generating system, a green roof system, or a combination thereof, is installed."

3.6.4.2 SOLAR PANELS (PHOTO-VOLTAIC CELLS) & SOLAR GEYSERS

The Facilities Management Company intends to provide all private developments with solar generated electricity as a package offer included with the site. Details to follow.

Solar panels are only allowed on the main double pitch of a roof, in line with the slope of the roof. No solar panels are allowed on any secondary roofs. No solar panels are allowed on frames with a different slope than the roof.

Solar Panels must have a black trim around the edges and must be integrated with the overall roof aesthetic.

3.6.4.3. STOEPS AND VERANDAS

(i) Stoeps must be coherent and complement the core building in design and use of materials.

(ii) Stoeps may be covered with a lean-to roof of which the minimum gradient must be 15° (if the roof is exposed on elevation) to create a veranda. The roofing material must be the same as used on the core building. The underside of the roof structure may be exposed or a ceiling may be installed.

(iii) Alternatively stoeps can be covered with a pergola with evenly spaced rafters or may be left uncovered. It is recommended that vines or other suitable creepers are used to cover pergolas. Rafters for pergolas may be of rolled steel section, balance of the members to be of timber or a timber profiled material and finished in oil or varnish for timber or paint or equal for any other materials.

(iv) Private stoeps not visible from the street may be covered with flat roofs behind horizontal parapet walls.

(v) The same roofing material is to be used for all pitched roofs on a particular site.

3.6.5. WINDOWS, SHUTTERS AND EXTERNAL DOORS

3.6.5.1 FINISHES INCLUDE:

(i) Timber - natural (oil or varnish finish).

(ii) Timber - painted black, dark grey, white or to accent colour specifically approved by the Developer's Assessment Panel.

(iii) Aluminum - powder / epoxy coated in black, dark grey, white or to accent colour specifically approved by the Developer's Assessment Panel.

3.6.5.2 Window proportions shall be either square or such that height exceeds width.

3.6.5.3 Corner windows are permitted subject to compliance with proportion controls and overhangs.

3.6.5.3 In the event that burglar bars are fitted these must be internal and should be aligned with the windows, mullions and transoms.

3.6.5.4 Large doors and windows will be permitted where screened or recessed a minimum of 1500mm behind the outer line of a pergola, veranda or other accepted shading device.

3.6.5.5 Front doors shall be simple and to match the windows and door in material and finishes. Frameless glass doors will be permitted subject to being recessed 1500mm behind a shading element. Handles and ironmongery should be selected to suit the Stellenbosch Bridge aesthetic.

3.6.5.6 Shutters which are strongly encouraged, must be sliding and framed with a frame of not less than 50mm. Shutter tracks should be integrated into the design through use of recesses and panels.

3.6.5.7 Shutter colours are either to be natural timber, white or to match the external window and door colour. Any alternative colours are to be specifically submitted to the Developer's Assessment Panel for approval.

3.6.5.8 Glazing shall be clear except where UV protection is required where a grey or smoke tint may be permitted. Note that where this is intended it must be clearly stated on the building plan submission. Coloured tints (other than grey) as well as silver or other metallic colours, tints, interlayers or films are specifically prohibited.

3.6.5.9 Window sills and surrounds are to be simple and no decorative or figurative moldings or sills are permitted.

3.6.5.10 GABLE WINDOWS

(i) These windows must always be of a vertical proportion,

(ii) The width of openings on gable walls may not exceed 40% of the width of the gable wall.

Images showing examples of window and door applications.

3.6.6. HANDRAILS AND BALUSTRADES

(i) External balustrades may be of a steel type and be composed of horizontal and vertical steel. All balustrades to be black, white or a dark grey unless prior approval is obtained from the Developer's Assessment Panel.

(ii) External balustrades may be of frameless glass subject to having simple masonry piers at corners and changes of direction.

(iii) Timber handrails will be allowed to be fixed above the steel posts and balustrades must be fully indicated on the submission.

3.6.7. COLUMNS AND PILLARS

i) Masonry columns are to be simple square section columns, simple plastered capitals and bases will be permitted.

ii) Columns of timber or rolled steel sections will be permitted.

3.6.8.BOUNDARY WALLS

(i) Boundary walls for Street facade boundaries facing onto the estate road and boundaries facing onto internal green or public open spaces include:

- Low masonry walls with a simple defined base and coping and a maximum height not exceeding 1200mm will be permitted along these boundaries.
- Visually permeable, high quality fencing will be allowed at the discretion of the Developer's Assessment Panel.
- Street facing boundary walls to be placed in line with or at the back of street facing office facade.

(ii) Perimeter boundaries not facing the street should not exceed 3000mm in height and are comprised of:

- Masonry walls with a simple defined base and coping.
- Visually permeable, high quality fencing will be allowed at the discretion of the Developer's Assessment Panel.

(iii) No gates shall be higher than the adjoining wall and full detail of any gates is required with the submission.

(iv) Precast cement walls or timber fences will not be permitted.



Street Facing Boundary



Perimeter Boundaries

Images showing examples of handrail and column applications.

Indicative Look and Feel Images for Industrial Precinct

3.7. GENERAL DESIGN GUIDELINES AND RESTRICTIONS

3.7.1 MECHANICAL EQUIPMENT

3.7.1.1 Mechanical equipment and plant such as air-conditioners (and grilles), ducts, pumps, etc, must be designed into the buildings and / or adequately enclosed or screened off from view from adjoining streets. The position of all these units is to be specifically marked on the submission and all screens to be fully detailed on submission. No exposed trunking will be allowed.

3.7.1.2 Water tanks are permitted where fully below ground or completely contained within a structure fully meeting the requirements of the guideline. Any plumbing and pipework to be suitably concealed and fully detailed on the submission.

3.7.1.3 All plumbing and mechanical pipes are to be suitably concealed within walls or ducts and may not be exposed to the exterior.

3.7.2 AERIALS, SATELLITE DISHES

3.7.2.1 No satellite dishes, TV aerials and radio antennas are allowed.

3.7.3. GREY WATER, GROUND WATER AND RAIN WATER TANKS

3.7.3.1 The use of grey water is promoted as an additional source of irrigation. The Developers Assessment Panel must approve the system that will be used for grey water recycling.

3.7.3.2 The installation of greywater and rainwater tanks should be incorporated into the design of the building.

3.7.3.3 Care must be taken to ensure that the correct filtration system is in place to prevent health risks.

3.7.3.4 No private boreholes may be sunk within the Estate.

3.7.3.5 The Developers Assessment Panel must approve the system that will be used for rainwater harvesting and any other methods other than a water tank that are used to store rain water. The Developers Assessment Panel must approve the position of the water tank or the screen method to be used to hide visually obscure the tank from the road.

3.7.3.6 No wind turbines are allowed on the estate.

3.7.4. ENERGY SAVING GUIDELINES

3.7.4.1 All buildings must comply to the SANS 10400 Part XA and SANS 204 Energy saving guidelines.

3.7.4.2 Solar panels must be placed flat on angled or flat roof sections with the correct orientation. All tanks related to solar geysers to be placed inside the roof.

3.7.4.3 All heat pump systems to be placed on ground level and screened.

3.7.3.4 A list of preferred suppliers of solar specialists is available from the Developer's office.

3.7.3.5 The use of gas hobs are encouraged. All gas items and installations to be the Developer's accredited supplier.

3.7.3.6 All photovoltaic systems to be registered with Eskom by the registered owner.

3.7.5 LIGHTING

All external lighting is only to be done on approval by Developer's Assessment Panel.

3.7.5.1 External lighting should compliment the architecture and enhance the façade, rather than overpower it.

3.7.5.2 All external lighting, including type, fixture and colour must be indicated on stage 2 plans. Only lights from the accredited Estate supplier will be allowed.

3.7.5.3 Lighting should be unobtrusive and low-level and the light source should not be visible from outside the site.

3.7.5.4 Bright security lighting or coloured lights will not be allowed.

3.7.5.5 Lighting of garden features should be done minimally to limit light pollution.

3.7.6. SIGNAGE
(Refer to Signage Strategy)

All signage must be in line with the Signage Guidelines (Section 6) located in the Stellenbosch Bridge Development Manual.

3.7.6.1 Under no circumstances will advertising boards or advertising bins be allowed anywhere on the Estate, unless expressly approved by the Developers Assessment Panel.

3.7.6.2 Neon signage should be avoided. Signage that does not compliment the style or character of the Estate will not be allowed.

3.7.6.3 All signage related to marketing and construction will be as per the Signage Guidelines.(Section 6) located in the Stellenbosch Bridge Development Manual.

3.7.7 DECORATIVE AND OTHER OUTDOOR ELEMENTS

3.7.7.1 Any outdoor elements such as benches, bins, sculptures, pots or any outdoor elements must be approved by the Developers Assessment Panel. Elements must conform to the general ethos of the Stellenbosch Bridge Estate.

3.7.8. SERVICE CONNECTIONS

3.7.8.1 Detailed layout diagrams are available for all civil and data service connections from the Developer.

3.7.9. GENERAL

3.7.9.1 Outbuildings and additions should match the original building design in style, elevation and material usage.

3.7.9.2 Buildings on slopes must be designed in response to the slope of the site on stepped building platforms as may be agreed to with the Developer's Assessment Panel.

3.8. STREET AND PUBLIC SPACE ELEMENTS

3.8.1 HARD LANDSCAPING

Basic guidelines are given below. These deal with the practicalities of function, materials, selection and siting.

The following hard landscape elements are identified:

a) Hard Surfaces:
A consistent layout of paving materials and patterns contribute to unique streetscapes and will provide a distinctive identity to Stellenbosch Bridge Estate. Paving also gives a sense of continuity between different areas, particular where a single material is used for edges and channels. Subtle variations in colour and texture help to provide contrast, richness and a sense of scale.

3.8.2 PEDESTRIAN WALKWAYS

- Haunching of paved areas may not be exposed.
- Surface texture should respond to the type of pedestrian movement.
- Textured surfaces for slow moving pedestrians or stationary pedestrians where benches occur.
- Even surfaces for faster moving pedestrians along desired lines and sidewalks.
- Where trees are planted into the paving, the porosity of the paving material should be considered.
- Spaced pavers with gravel or planting infill would allow water and air to reach tree roots.
- Patterns in paved areas should follow and accommodate expansion joints.
- A pathway to the entrance of a house may not exceed 1,5m in width.
- A driveway and pathway access may not be built adjacent to each other to form a continuous paved area.
- All paved areas must be constructed as per standard building practices to ensure an even surface. All paving edges must also be laid evenly, flush with ground level, on a concrete footing and edge the entire length of the driveway/path.

The following materials may be used for pathways:

Bosun Kalahari, 200 x 100 x 60mm exposed aggregate

De Hoop Red Paver, 200 x 98,5 x 50mm

All paving to Developers Assesment Panel Approval.

3.8.3 DRIVEWAYS AND PARKING AREAS

- Haunching of paved areas may not be exposed.
- A driveway and pathway access may not be built adjacent to each other to form a continuous paved area.
- All paved areas must be constructed as per standard building practices to ensure an even surface. All paving edges must also be laid evenly, flush with ground level, on a concrete footing and edge the entire length of the driveway/path.
- Paving should be designed with cross falls to act as a self cleaning mechanism and to limit water to collect on the paving that results in discoloration and slippery surfaces.
- Channels may be incorporated in the edge/center patterning to allow run-off of surface water.

Driveway materials are to be a combination of Smartstone (or similar) concrete cobble (charcoal or grey colour) clay brick pavers, or exposed concrete surface beds for heavy duty areas.

Images showing examples of street and pavement surface applications.

Integrated Public Realm

3.8.4 EXTERNAL LIGHTING

All external lighting is only to be done on approval by Developer's Assessment Panel.

External lighting should compliment the architecture and enhance the façade, rather than overpower it. Lighting of garden features should be done minimally to limit light pollution.

3.8.5 PUBLIC WAY FINDING SIGNAGE

Way finding signage and bollards are provided and maintained by the Developer in public spaces.

3.8.6. RETAINING ELEMENTS

- Retaining levels for houses, buildings and or landscape elements may not exceed 1m above natural ground. All retaining levels to be clearly dimensioned as part of building plan submissions.

3.8.7.STORMWATER MANAGEMENT

- Stormwater servitudes are provided in some cases and must be adhered to.
- Where servitudes are not provided the lower property must accept and channel the higher property's stormwater to the closest road stormwater system.
- Refer to Landscaping Guideline Document (Annexure G).

3.8.8 GENERAL STREET AND PUBLIC SPACE ELEMENTS

Manholes:
- Where possible the position of manhole covers should be integrated into the paving pattern and aligned with buildings, so that brick and slab cutting are kept to a minimum.

Steps and ramps:
- Steps and ramps are seen as another dimension of paving, accommodating changes in levels, helping to define spaces and even providing outdoor seating.
- Illumination of a change of level is encouraged, particularly at the foot and top of a flight.
- All steps and ramps should adhere to the Standard Building Regulations.

Planters:
- Plant containers may be used where trees and shrubs cannot be planted directly in to the ground and in conjunction with seating, steps and retaining walls.
- They may also be used to form barriers, provide screening or soften high walls.
- Brick (plastered and painted), clay or re-enforced concrete planters may be used.
- No pots will be allowed in landscape control areas. Freestanding pots will be subject to the approval of the Control Landscape Architect.
- Pots should match existing colour schemes of surrounding estate and are not allowed to be excessively decorative.

Flowerbed edging:
- Flowerbeds will not be edged with stones, bricks, timber etc. when adjacent to lawned areas. Only specified products may be used.
- Edging is allowed when used as a design determinant (i.e. accent lines) and is to be pre-approved by the Control Landscape Architect.
- Any level difference between flowerbeds and lawn/hard surfaces greater than 150mm is to be retained by means of a plastered and painted low cape wall up to a maximum height of 1200mm. It is however advisable to rather create a gentle slope when the level difference is less than 300mm.

Images showing examples of street and pavement surface applications.

ARCHITECTURAL CODES AND GUIDELINES FOR INDUSTRIAL PRECINCTS

KEY:

PRECINCTS 1 AND 2 SOUTH

PRECINCT 2 NORTH



Stellenbosch Bridge Masterplan - Light Industrial Precincts

SECTION 4 - ARCHITECTURAL CODES AND GUIDELINES FOR INDUSTRIAL PRECINCT 2 NORTH

(SEE SEPERATE CODES AND GUIDELINES FOR SOUTHERN PRECINCTS)

4.1. URBAN DESIGN ELEMENTS

4.1.1 BUILT FORM AND SCALE

4.1.1.1. Site consolidations will be favorably considered, especially for irregular stands that will be more usable if consolidated.



Example of Typical Industrial Site



Plan of Typical Industrial Site

4.1.1.2 HEIGHT OF BUILDINGS

HEIGHT OF BUILDINGS - Na Area

Maximum Height at Apex 16m
Maximum height at Eaves 12m

HEIGHT OF BUILDINGS-Nb + S Areas

Maximum Height at Apex 18m
Maximum height at Eaves 12m

Office portions of the buildings to be a maximum of two storeys high

(Subject to planning approval)

LIGHT INDUSTRIAL PRECINCT

INNOVATION PRECINCT

Maximum Eaves Height : 12m
Maximum Apex Height : 18m

Maximum Eaves Height : 12m
Maximum Apex Height : 16m

4.1.2 FACADE

• The facade towards the dominant external roads and railways should be of a corporate character. The warehouse component of the building that is visible from the road should be treated as a commercial façade.

• The façade of the building along the external roads is expected to cover a substantial portion of the site width.

Façade extensions concealing side yards may form part of the façade.

4.1.3 BUILDING ENVELOPE

• The office and warehouse components of the building should be designed in good proportional relation.

• Minimum pitched warehouse structures are encouraged.

• Roofs should be addressed as part of the building envelope design.

4.1.4 PLINTHS

• Plastered brick, face brick and concrete plinths are to be designed in good proportion to the envelope.

4.1.5 LEGIBILITY

• Buildings on prominent corners and intersections have to be enhanced in form and material to emphasize and utilize the prominent position.

• Signage and way-finding must be clear but sophisticated and presented for approval to the Developer's Assessment Pane with the stage 02 submission drawings

4.2. MATERIALS AND QUALITY OF WORK

4.2.1 Building materials of a high quality are to be used in order to ensure the structural integrity of the buildings over time, and to maintain their appearance.

4.2.2 Within the constraints of the colour code a wide range of materials is possible.

4.2.3 In general, materials which are high quality and low maintenance and which assist in the expression of the architecture should be used.

4.2.4 All materials and their application are to be to the satisfaction of the Developer's Assessment Panel whose judgment will be directed by, but not limited to, the extent to which any material is integral to achieving a high quality, architectural design.

4.2.5 All materials should have an adequate record of application in the local climatic conditions.

4.2.6 High quality materials such as suitably treated glass, anodised or coated aluminum, stainless steel, and natural stone are acceptable and encouraged. Other high quality products will be considered but only at the discretion of the Developer's Assessment Panel.

4.2.7 All surface coatings are to be long lasting, enduring in quality and appearance with low to moderate maintenance needs.

4.2.8 Wall materials may vary from high quality masonry block to sealed or painted textured plaster surface, suitable stone and offshutter concrete.

4.2.9 The choice of materials should reflect energy conservation consciousness, appropriate to the building's use.

4.2.10 All buildings should have articulated façades with the use of shading devices, and generous overhangs strongly encouraged.

4.2.11 The latest issues of specifications, regulations and codes of practice (e.g. SABS/SANS specifications) shall be applicable. Wherever the SABS/SANS has prepared specifications for materials or products, such materials or products, are to be made and supplied to the Bureau's specification, and further, where materials and products are manufactured by Permit Holders of the SABS, such materials and products must be supplied with the SABS/SANS Codes of Practice.

4.3 COLOURS AND TEXTURES

4.3.1 A range of white; dark greys, natural stone; and timber should be used as a unifying theme of all architecture throughout the Industrial area.

4.3.2 THE FOLLOWING WALL FINISHES ARE PERMITTED:

(i) Smooth plaster and paint. (colour to the approved palette)

(ii) A limited extent of fairface brickwork as a feature element, to the extent specifically approved by the committee, with paint finish. (colour to approved palette).

(iii) Integral coloured rendered wall coatings such as Marmoran, Gama Zenith and Earthcote. (colour to the approved palette)

(iv) Smooth off shutter. (Class 1) concrete, unpainted)

(v) Designers are encouraged to use the wall finishes in combinations.

4.3.3 LIST OF SUGGESTED / PREFERRED COLOURS & TEXTURES:

(i) General - white to grey, sand to taupe, monochromatic as shown.

(ii) A single field colour and accent colour may be chosen from the following approved colour palette.

The approved palettes are: (Plascon or equal paint colours)

- FIELD
  AW: Arniston White;
  AW: Arniston White 50% LT;
  CAS 1, WHITE.
- ACCENT
  B5-E1-3 Gravel Road;
  B5-E2-2 Grimsby;
  B5-E2-3 Whisper.

Note that the location and extent of any accent colour must be marked on the submission drawings for approval.

4.4 FEATURE ELEMENTS COLOUR PALETTE

ROOFS, DOORS, WINDOW SHUTTERS & FRAMES, BALUSTRADES & OTHER

The colours of feature elements are limited to the monochrome palette.

Certain feature elements of different colours or materials might be approved by the panel, on a discretionary basis.

By keeping the roof colours and feature element colours in the same monochrome tones, it gives the estate a uniform appearance and contemporary style.

Alternative accent colours may be permissible subject to approval by the Developer's Assessment Panel .

Images showing the muted colour palette and range of textures for SBB

4.5. ARCHITECTURAL CODES: ELEMENTS OF THE BUILDING

4.5.1 FAÇADE TREATMENT: HORIZONTAL TREATMENT & VERTICAL MODULATION

(i) The manner in which the building meets the ground must be addressed positively: a plinth or base is suggested.

4.5.2 FAÇADE MATERIALS AND COLOURS

The facade treatment should follow the general guidelines for materials and colours, as specified for Stellenbosch bridge.

4.5.3 SHADING DEVICES

(i) Buildings are required to be energy efficient and must include passive solutions to climate control to reduce reliance on mechanical solutions.
Such approaches include facade layering, shading of glass, suitable shading of north, east and west facades.

(ii) Most sun-screening devices such as balconies, colonnades, canopies, awnings, eaves, overhangs and multi-planar façades are encouraged.

(iii) Where heat-retardant glass is to be used, and subject to the materials specification in Annexure E, reflective mirror-faced glazing is not permitted.

Images showing articulated facades, with visually permeable fronts, with recesses and overhangs

4.5.4 ROOFING

(i) Permitted materials include:

- **High quality seamless fix, factory colour coated roof sheeting**
- **Concrete trafficable roof** with appropriate finish, drainage, insulation and waterproofing
- **'Green Roof'** – consisting of appropriate planting on fill on a Concrete roof with appropriate drainage, insulation and waterproofing.

(ii) The roof should be considered as an integral aesthetic component of the building. The architecture must consider the relationship of the building to the skyline and to adjacent developments when viewed from various perspectives.

(iii) All roof pitches should not to exceed 40°.

(iv) Gable walls may project above the roof surface as parapets or may terminate at the roof surface in which case the roof covering must be carried over the head of the wall to form a verge (barge board).

(v) The top of the gable end walls must consist of straight and simple lines and may not have rounded elements. It is recommended that these elements be kept simple and without any elaborate decoration, however plain/simple plaster copings over the top of these walls are permissible; and the line of the gable wall must always follow the pitch of the roof line except where flat roofs has been used.

(vi) Roofs must have clipped or flush eaves on the longitudinal side of the building.

(vii) Roofs may not project on the gable end side.

(viii) Any equipment required at roof level must be suitably concealed and may not be exposed to the exterior and must be approved by the Developer's Assessment Panel. No satellite dishes, TV aerials and radio antennas allowed.

(ix) Provision must be made by owners for a network connection. A full guideline pertaining to network connections can be found in the Technical Guidelines.

(ix) Long spanned roofs must favor a north-south orientation.

(x) All roofs to be a dark monochrome colour from the Feature Elements colour palette in this Manual. Garage & carport roofs must match the material & colour of the main structures.

THE FOLLOWING MATERIALS MAY BE UTILISED:

- Any profile metal sheeting. Colours to match Feature Elements palette. It must conform to the contemporary feel of the estate.
- Visible translucent sheeting should be clearly marked on the drawings.

THE FOLLOWING MATERIALS MAY NOT BE UTILISED:

- Tiles are not allowed

MATERIALS & COLOURS FOR FLAT ROOFS

- Flat concrete roofs can be planted or covered with loose stone.
- Fascias, barge boards to match roof or wall colours.
- Gutters to match roof colours or wall colours.
- Eaves without gutters are allowed if building is provided with apron.
- No PVC gutters or downpipes to be used.

Images illustrating the roof as an integral part of the building aesthetic.

4.5.4.1 SUSTAINABLE ROOFS

Sustainable roofing zones are defined as "areas of a roof assembly where a solar photovoltaic electricity generating system, a green roof system, or a combination thereof, is installed."

4.5.4.2 SOLAR PANELS (PHOTO-VOLTAIC CELLS) & SOLAR GEYSERS

The Facilities Management Company intends to provide all private developments with solar generated electricity as a package offer included with the site. Details to follow.

Solar panels are only allowed on the main double pitch of a roof, in line with the slope of the roof. No solar panels are allowed on any secondary roofs. No solar panels are allowed on frames with a different slope than the roof.

Solar Panels must have a black trim around the edges and must be integrated with the overall roof aesthetic.

4.5.4.3. STOEPS AND VERANDAS

(i) Stoeps must be coherent and complement the core building in design and use of materials.

(ii) Stoeps may be covered with a lean-to roof of which the minimum gradient must be 15° (if the roof is exposed on elevation) to create a veranda. The roofing material must be the same as used on the core building. The underside of the roof structure may be exposed or a ceiling may be installed.

(iii) Alternatively stoeps can be covered with a pergola with evenly spaced rafters or may be left uncovered. It is recommended that vines or other suitable creepers are used to cover pergolas. Rafters for pergolas may be of rolled steel section, balance of the members to be of timber or a timber profiled material and finished in oil or varnish for timber or paint or equal for any other materials.

(iv) Private stoeps not visible from the street may be covered with flat roofs behind horizontal parapet walls.

(v) The same roofing material is to be used for all pitched roofs on a particular site.

4.5.5.COLUMNS AND PILLARS

i) Masonry columns are to be simple square section columns, simple plastered capitals and bases will be permitted.

ii) Columns of timber or rolled steel sections will be permitted.

4.5.6. BOUNDARY WALLS

- Visually permeable, high quality fencing will be allowed at the discretion of the Developer's Assessment Panel.

(i) Perimeter boundaries not facing the street should not exceed 3000mm in height and are comprised of:

- Masonry walls with a simple defined base and coping.

- Visually permeable, high quality fencing will be allowed at the discretion of the Developer's Assessment Panel.

(ii) No gates shall be higher than the adjoining wall and full detail of any gates is required with the submission.

(iii) Precast cement walls or timber fences will not be permitted.

Images showing examples of handrail and column applications.



Street Facing Boundary



Perimeter Boundaries

Indicative Look and Feel Images for Industrial Precinct

4.6. GENERAL DESIGN GUIDELINES AND RESTRICTIONS

4.6.1 MECHANICAL EQUIPMENT

4.6.1.1 Mechanical equipment and plant such as air-conditioners (and grilles), ducts, pumps, etc, must be designed into the buildings and / or adequately enclosed or screened off from view from adjoining streets. The position of all these units is to be specifically marked on the submission and all screens to be fully detailed on submission. No exposed trunking will be allowed.

4.6.1.2 Water tanks are permitted where fully below ground or completely contained within a structure fully meeting the requirements of the guideline. Any plumbing and pipework to be suitably concealed and fully detailed on the submission.

4.6.1.3 All plumbing and mechanical pipes are to be suitably concealed within walls or ducts and may not be exposed to the exterior.

4.6.2 AERIALS, SATELLITE DISHES

4.6.2.1 No satellite dishes, TV aerials and radio antennas are allowed.

4.6.3. GREY WATER, GROUND WATER AND RAIN WATER TANKS

4.6.3.1 The use of grey water is promoted as an additional source of irrigation. The Developers Assessment Panel must approve the system that will be used for grey water recycling.

4.6.3.2 The installation of greywater and rainwater tanks should be incorporated into the design of the building.

4.6.3.3 Care must be taken to ensure that the correct filtration system is in place to prevent health risks.

4.6.3.4 No private boreholes may be sunk within the Estate.

4.6.3.5 The Developers Assessment Panel must approve the system that will be used for rainwater harvesting and any other methods other than a water tank that are used to store rain water. The Developers Assessment Panel must approve the position of the water tank or the screen method to be used to hide visually obscure the tank from the road.

4.6.3.6 No wind turbines are allowed on the estate.

4.6.4. ENERGY SAVING GUIDELINES

4.6.4.1 All buildings must comply to the SANS 10400 Part XA and SANS 204 Energy saving guidelines.

4.6.4.2 Solar panels must be placed flat on angled or flat roof sections with the correct orientation. All tanks related to solar geysers to be placed inside the roof.

4.6.4.3 All heat pump systems to be placed on ground level and screened.

4.6.4.4 A list of preferred suppliers of solar specialists is available from the Developer's office.

4.6.4.5 The use of gas hobs are encouraged. All gas items and installations to be the Developer's accredited supplier.

4.6.4.6 All photovoltaic systems to be registered with Eskom by the registered owner.

4.6.5 LIGHTING

All external lighting is only to be done on approval by Developer's Assessment Panel.

4.6.5.1 External lighting should compliment the architecture and enhance the façade, rather than overpower it.

4.6.5.2 All external lighting, including type, fixture and colour must be indicated on stage 2 plans. Only lights from the accredited Estate supplier will be allowed.

4.6.5.3 Lighting should be unobtrusive and low-level and the light source should not be visible from outside the site.

4.6.5.4 Bright security lighting or coloured lights will not be allowed.

4.6.5.5 Lighting of garden features should be done minimally to limit light pollution.

4.6.6. SIGNAGE
(Refer to Signage Strategy)

All signage must be in line with the Signage Guidelines (Section 6) located in the Stellenbosch Bridge Development Manual.

4.6.6.1 Under no circumstances will advertising boards or advertising bins be allowed anywhere on the Estate, unless expressly approved by the Developers Assessment Panel.

4.6.6.2 Neon signage should be avoided. Signage that does not compliment the style or character of the Estate will not be allowed.

4.6.6.3 All signage related to marketing and construction will be as per the Signage Guidelines.(Section 6) located in the Stellenbosch Bridge Development Manual.

4.6.7 DECORATIVE AND OTHER OUTDOOR ELEMENTS

4.6.7.1 Any outdoor elements such as benches, bins, sculptures, pots or any outdoor elements must be approved by the Developers Assessment Panel. Elements must conform to the general ethos of the Stellenbosch Bridge Estate.

4.6.8. SERVICE CONNECTIONS

4.6.8.1 Detailed layout diagrams are available for all civil and data service connections from the Developer.

4.6.9. GENERAL

4.6.9.1 Outbuildings and additions should match the original building design in style, elevation and material usage.

4.6.9.2 Buildings on slopes must be designed in response to the slope of the site on stepped building platforms as may be agreed to with the Developer's Assessment Panel.

4.7. STREET AND PUBLIC SPACE ELEMENTS

4.7.1 HARD LANDSCAPING

Basic guidelines are given below. These deal with the practicalities of function, materials, selection and siting.

The following hard landscape elements are identified:

a) Hard Surfaces:
A consistent layout of paving materials and patterns contribute to unique streetscapes and will provide a distinctive identity to Stellenbosch Bridge Estate. Paving also gives a sense of continuity between different areas, particular where a single material is used for edges and channels. Subtle variations in colour and texture help to provide contrast, richness and a sense of scale.

4.7.2 PEDESTRIAN WALKWAYS

- Haunching of paved areas may not be exposed.
- Surface texture should respond to the type of pedestrian movement.
- Textured surfaces for slow moving pedestrians or stationary pedestrians where benches occur.
- Even surfaces for faster moving pedestrians along desired lines and sidewalks.
- Where trees are planted into the paving, the porosity of the paving material should be considered.
- Spaced pavers with gravel or planting infill would allow water and air to reach tree roots.
- Patterns in paved areas should follow and accommodate expansion joints.
- A pathway to the entrance of a house may not exceed 1,5m in width.
- A driveway and pathway access may not be built adjacent to each other to form a continuous paved area.
- All paved areas must be constructed as per standard building practices to ensure an even surface. All paving edges must also be laid evenly, flush with ground level, on a concrete footing and edge the entire length of the driveway/path.

The following materials may be used for pathways:

Bosun Kalahari, 200 x 100 x 60mm exposed aggregate

De Hoop Red Paver, 200 x 98,5 x 50mm

All paving to Developers Assesment Panel Approval.

4.7.3 DRIVEWAYS AND PARKING AREAS

- Haunching of paved areas may not be exposed.
- A driveway and pathway access may not be built adjacent to each other to form a continuous paved area.
- All paved areas must be constructed as per standard building practices to ensure an even surface. All paving edges must also be laid evenly, flush with ground level, on a concrete footing and edge the entire length of the driveway/path.
- Paving should be designed with cross falls to act as a self cleaning mechanism and to limit water to collect on the paving that results in discoloration and slippery surfaces.
- Channels may be incorporated in the edge/center patterning to allow run-off of surface water.

Driveway materials are to be a combination of Smartstone (or similar) concrete cobble (charcoal or grey colour) clay brick pavers, or exposed concrete surface beds for heavy duty areas.

Images showing examples of street and pavement surface applications.

Integrated Public Realm

4.7.4 EXTERNAL LIGHTING

All external lighting is only to be done on approval by Developer's Assessment Panel.

External lighting should compliment the architecture and enhance the façade, rather than overpower it. Lighting of garden features should be done minimally to limit light pollution.

4.7.5 PUBLIC WAY FINDING SIGNAGE

Way finding signage and bollards are provided and maintained by the Developer in public spaces.

4.7.6. RETAINING ELEMENTS

- Retaining levels for houses, buildings and or landscape elements may not exceed 1m above natural ground. All retaining levels to be clearly dimensioned as part of building plan submissions.

4.7.7.STORMWATER MANAGEMENT

- Stormwater servitudes are provided in some cases and must be adhered to.
- Where servitudes are not provided the lower property must accept and channel the higher property's stormwater to the closest road stormwater system.
- Refer to Landscaping Guideline Document (Annexure G).

4.7.8 GENERAL STREET AND PUBLIC SPACE ELEMENTS

Manholes:
- Where possible the position of manhole covers should be integrated into the paving pattern and aligned with buildings so that brick and slab cutting are kept to a minimum.

Steps and ramps:
- Steps and ramps are seen as another dimension of paving, accommodating changes in levels, helping to define spaces and even providing outdoor seating.
- Illumination of a change of level is encouraged, particularly at the foot and top of a flight.
- All steps and ramps should adhere to the Standard Building Regulations.

Planters:
- Plant containers may be used where trees and shrubs cannot be planted directly in to the ground and in conjunction with seating, steps and retaining walls.
- They may also be used to form barriers, provide screening or soften high walls.
- Brick (plastered and painted), clay or re-enforced concrete planters may be used.
- No pots will be allowed in landscape control areas. Freestanding pots will be subject to the approval of the Control Landscape Architect.
- Pots should match existing colour schemes of surrounding estate and are not allowed to be excessively decorative.

Flowerbed edging:
- Flowerbeds will not be edged with stones, bricks, timber etc. when adjacent to lawned areas. Only specified products may be used.
- Edging is allowed when used as a design determinant (i.e. accent lines) and is to be pre-approved by the Control Landscape Architect.
- Any level difference between flowerbeds and lawn/hard surfaces greater than 150mm is to be retained by means of a plastered and painted low cape wall up to a maximum height of 1200mm. It is however advisable to rather create a gentle slope when the level difference is less than 300mm.

Images showing examples of street and pavement surface applications.

ANNEXURE E

	TYPICAL OFFICE / COMMERCIAL	TYPICAL INDUSTRIAL	RESIDENTIAL	RETAIL	OTHER
Roof	A: Flat concrete roof or flat concrete roof with landscaping (green roof); B: Visible pitched roof- metal profiled sheeting, colour treated (dark grey); C: Low pitched metal roof to be concealed behind parapet; No concrete/ clay tiles. Flat roofs to have trafficable surface. Sculptural roof elements permitted to enhance entrances or at landmark situations (as identified on land parcel sheets), subject to assessment panel approval.	A: Flat concrete roof or flat concrete roof with landscaping (green roof); B: Visible pitched roof- metal profiled sheeting, colour treated (dark grey); C: Low pitched metal roof to be concealed behind parapet; No concrete/ clay tiles. Flat roofs to have trafficable surface. Sculptural roof elements permitted to enhance entrances or at landmark situations (as identified on land parcel sheets), subject to assessment panel approval.	A: Flat concrete roof or flat concrete roof with landscaping (green roof); B: Visible pitched roof- metal profiled sheeting, colour treated (dark grey); C: Low pitched metal roof to be concealed behind parapet; No concrete/ clay tiles. Flat roofs to have trafficable surface. Sculptural roof elements permitted to enhance entrances or at landmark situations (as identified on land parcel sheets), subject to assessment panel approval.	A: Flat concrete roof or flat concrete roof with landscaping (green roof); B: Visible pitched roof- metal profiled sheeting, colour treated (dark grey); C: Low pitched metal roof to be concealed behind parapet; No concrete/ clay tiles. Flat roofs to have trafficable surface. Sculptural roof elements permitted to enhance entrances or at landmark situations (as identified on land parcel sheets), subject to assessment panel approval.	Green Roofs Encouraged.
External / Vertical Surface Treatment / Walls	Majority of facade to be white rendering/ plaster. Natural stone; facebrick; off shutter concrete; timber and metal sheeting accents.	External White Plaster. Metal sheeting accents.	Majority of facade to be white rendering/ plaster. Natural stone; facebrick; off shutter concrete; timber and metal sheeting accents.	Majority of facade to be white rendering/ plaster. Natural stone; facebrick; off shutter concrete; timber and metal sheeting accents.	
Windows / Fenestration	Vertical proportioned aluminum or timber (painted or natural) frames/ mullions. ; openable; curtain wall type/ glazing as accent; deep recesses are encouraged; no mirror glass. No continuous strip windows - at lower and intermediate levels, individually identifiable elements required. Curtain walling permitted only at entrances or for specific effect, and subject to assessment panel approval.	Vertical proportioned aluminum or timber (painted or natural) frames/ mullions. ; openable; curtain wall type/ glazing as accent; deep recesses are encouraged; no mirror glass. No continuous strip windows - at lower and intermediate levels, individually identifiable elements required. Curtain walling permitted only at entrances or for specific effect, and subject to assessment panel approval.	Vertical proportioned aluminum or timber (painted or natural) frames/ mullions. ; openable; curtain wall type/ glazing as accent; deep recesses are encouraged; no mirror glass. No continuous strip windows - at lower and intermediate levels, individually identifiable elements required. Curtain walling permitted only at entrances or for specific effect, and subject to assessment panel approval.	Vertical proportioned aluminum or timber (painted or natural) frames/ mullions. ; openable; curtain wall type/ glazing as accent; deep recesses are encouraged; no mirror glass. No continuous strip windows - at lower and intermediate levels, individually identifiable elements required. Curtain walling permitted only at entrances or for specific effect, and subject to assessment panel approval.	Heat-retardant glass: no 'mirror' / highly reflective glazing.
Building base / Plinth	Natural stone/ Facebrick/ White plaster/ concrete or timber accents on plinths, lintels, plinths, feature walls.	Natural stone/ Facebrick/ White plaster/ concrete or timber accents on plinths, lintels, plinths, feature walls.	Natural stone/ Facebrick/ White plaster/ concrete or timber accents on plinths, lintels, plinths, feature walls.	Natural stone/ Facebrick/ White plaster/ concrete or timber accents on plinths, lintels, plinths, feature walls.	
Canopies / Sun shades	Metal frame with grating, etc; timber/ steel, colour to suite SB palette. As appropriate to location and facade design. Retractable canopy system permitted. Encouraged for ground floor retail frontages. Max canopy projection to full width of pavement. Canopies may be cantilevered or supported by a lightweight structure - subject to assessment panel approval.	Metal frame with grating, etc; timber/ steel, colour to suite SB palette. As appropriate to location and facade design. Retractable canopy system permitted. Encouraged for ground floor frontages. Max canopy projection to full width of pavement. Canopies may be cantilevered or supported by a lightweight structure - subject to assessment panel approval.	Metal frame with grating, etc; timber/ steel, colour to suite SB palette. As appropriate to location and facade design. Retractable canopy system permitted. Encouraged for ground floor retail frontages. Max canopy projection to full width of pavement. Canopies may be cantilevered or supported by a lightweight structure - subject to assessment panel approval.	Metal frame with grating, etc; timber/ steel, colour to suite SB palette. As appropriate to location and facade design. Retractable canopy system permitted. Encouraged for ground floor retail frontages. Max canopy projection to full width of pavement. Canopies may be cantilevered or supported by a lightweight structure - subject to assessment panel approval.	
Colonnades	Colonnades must wrap around building where applicable. Encouraged for ground floor retail frontages. Max canopy projection to full width of pavement.			Colonnades must wrap around building where applicable. Encouraged for ground floor retail frontages. Max canopy projection to full width of pavement.	
Landscaping	As per Section 5.	As per Section 5.	As per Section 5.	As per Section 5.	
Entrance Portal	Double Volume, shaded from sun.	Double Volume, shaded from sun.	Double Volume, shaded from sun.	Double Volume, shaded from sun.	
Colours	As per SB palette.	As per SB palette.	As per SB palette.	As per SB palette.	
Textures	As per SB palette.	As per SB palette.	As per SB palette.	As per SB palette.	
Signage	As per Section 6.	As per Section 6.	As per Section 6.	As per Section 6.	

STELLENBOSCH
BRIDGE | BHULORHO | BRUG

STELLENBOSCH
STELLENBOSCH • PNIEL • FRANSCHHOEK

MUNICIPALITY • UMASIPALA • MUNISIPALITEIT

ANNEXURE C

PLANT LIST

TREES - ALL DOUBLE-STAKED (100L TO 500L SIZE)
NOTE: TREES IN PARKING AREAS MINIMUM 100L SIZE

BRACHYLEANA DISCOLOR
BUDDLEJA SALIGNA
EKEBERGIA CAPENSIS
HARPEPHYLLUM CAFFRUM
PITTOSPORUM VIRIDIFLORUM
SYZYGIUM GUINEENSE
TARCHONANTHUS CAMPHORATUS

SHRUBS AND GROUNDCOVERS (3-7/M²)
ARISTEA MAJOR
AGAPANTHUS PRAECOX
ARCTOTIS SP.
ASYSTASIA GANGETICA
BARLERIA REPENS
CARISSA MACROCARPA
COLEONOMA ALBUM
DIETES GRANDIFLORA
ELEGIA CAPENSIS
ELEGIA TECTORUM
FICINIA NODOSA
GAZANIA SP.
HELICHRYSUM PETIOLARE
JUNCUS KRAUSII
PELARGONIUM SP.
PLECTRANTHUS CILIATUS
POLYGALA MYRTIFOLIA
SEARSIA CRENATA
TECOMA CAPENSIS
WATSONIA SP.

SWALES AND WETLANDS (3-7/M²)

APONOGETON DISTACHYOS
BOLBOSCHOENUS MARITIMUS
BULBOSCHOENUS MARITIMUS
CAREX CLAVATA
CHASMANTHE AETHIOPICA
CYPERUS TEXTILIS
ELEGIA SP
FICINIA NODOSA
ISOLEPSIS LUDWIGII
ISOLEPIS PROLIFER
JUNCUS EFFUSUS
MARSCUS THUNBERGII
NYMPHAEA CAPENSIS (BLUE)
RESTIO TESTUCIFORMIS
SCHOENOPLECTUS SP
SCIRPUS NODOSUS
THAMNOCHORTUS INSIGNIS
WACHENDORFIA THYRSIFLORA
ZANTEDESCHIA AETHIOPICA

NOTES:
SIDEWALK LANDSCAPING:

- TO BE INSTALLED PRIOR TO OCCUPATION
- TREES AS INDICATED TO BE 500L SIZE.
- SHRUBS TO BE INSTALLED AT A DENSITY OF 5/m² MINIMUM SIZE: FROM ECO-TRAY
- AN AUTOMATIC IRRIGATION SYSTEM, LINKED TO THE SITE / ERF TO BE INSTALLED
- MAINTENANCE BY ESTATE
- SIDEWALK PLANT LIST (5/m²)
- ARISTEA AFRICANA
- BARLERIA PURPLE
- CAPITATUM
- CUCULLATUM
- DIETES GRANDIFLORA
- FICINIA NODOSA
- FELICIA
- PELARGONIUM
- WATSONIA (SALMON)

GENERAL NOTES: PERTAINING TO ALL ERVEN (S1 TO S5, N1 TO N7):

- ALL FENCING & ELECTRICAL ISOLATORS TO BE BLACK.
- ALL LANDSCAPING TO HAVE A FULLY AUTOMATIC IRRIGATION SYSTEM.
- A LANDSCAPE PLAN MUST BE SUBMITTED TO THE ESTATE PRIOR TO SDP SUBMISSION TO COUNCIL.
- TREES IN PARKING AREAS: 1 x MINIMUM 100L SIZE PER 4 PARKING BAYS (UNLESS BAYS SIT AGAINST THE BUILDING.)
- AUTOMATIC IRRIGATION MUST BE INSTALLED TO ALL PLANTING STRIPS AND TREES.
- SIDEWALK PLANTING AND TREES MUST BE INSTALLED BY ERF DEVELOPER.
- 2 x 160Ø SLEEVES MUST BE INSTALLED UNDER ALL ACCESS ROADS (DRIVEWAYS.)
- SIDEWALK LANDSCAPING SHALL HAVE AUTOMATIC IRRIGATION LINKED TO THE IRRIGATION SYSTEM ON THE ERF.
- MAINTENANCE OF SITE LANDSCAPING, AS WELL AS SIDEWALK LANDSCAPING SHALL BE DONE BY THE ERF OWNER/ TENANT TO HOA STANDARDS.

NOTES:

1) AN IRRIGATION SYSTEM IS TO BE INSTALLED IN ALL PLANTED AREAS. SPRAYER OVERLAP TO BE 100%. ALL TREES TO HAVE IRRIGATION AS PART OF THE OVERALL SYSTEM. ALL PIPES AND FITTINGS TO BE SABS APPROVED AND TO THE LANDSCAPE ARCHITECTS APPROVAL. ALL IRRIGATION SLEEVES ARE TO BE 110mm Ø, POSITIONED 600mm BELOW FINISHED LEVEL OF ROAD KERBING OR PAVING, AND ARE TO EXTEND 600mm BEYOND EDGE OF ROAD KERBING OR PAVING. ALL SLEEVES ARE TO RUN TO THE SIDE OF TREE OPENINGS, NOT THE CENTRE.

2) ALL TREES TO BE STAKED USING 2x50mm DIA. TANALITH TREATED POLES DRIVEN 600mm INTO THE GROUND AND TIED BY MEANS OF TWO RUBBER HOSES AND WIRE OR COMMERCIAL TREE TIES. CARE MUST BE TAKEN NOT TO DAMAGE THE ROOT BALL OF THE TREE.



REVISIONS		
REV NO.	DESCRIPTION	TYPE OF ISSUE
00	DRAWING CREATED	FOR INFO.
01	DRAWING AMENDED & HATCHED	FOR INFO.
02	DRAWING AMENDED	FOR INFO.

FOR INFORMATION

STELLENBOSCH BRIDGE

LANDSCAPE MASTER PLAN

Drawing No: 2997 - 02 - MP - REV 02
Scale: 1:1000 @ A1 Date: 25 FEB 2025
Drawn by: EA Checked by: TdV

CNDV LANDSCAPE ARCHITECTS
tel: +27 21 810 7799
web: www.cndv.biz
5th floor, 6 Pepper Street,
Cape Town, 8001

STELLENBOSCH
STELLENBOSCH • PNIEL • FRANSCHHOEK

MUNICIPALITY • UMASIPALA • MUNISIPALITEIT

ANNEXURE D

AREA BIRDS EYE VIEW
NOT TO SCALE



SITE ACCESS LINE
NOT TO SCALE

VIA AND RESPONSE TO GUIDELINES - INDUSTRIAL PRECINCT 2 NORTH

1. BUILDING HEIGHT

APEX: 13,644MM MAX HEIGHT 16M
EAVES: 11,723MM MAX HEIGHT 12M
THE OFFICE SECTION DOES NOT EXCEED TWO STOREYS

2. FACADE

NORTH FACADE (FACING THE RAILWAY): DESIGNED WITH A CORPORATE AESTHETIC FEATURING CURTAIN WALLING

SOUTH FACADE (WAREHOUSE SECTION): TREATED AS A COMMERCIAL FACADE FOR A COHESIVE LOOK.

3. WALL & PLINTH TREATMENT

ALL WALLS WILL BE SMOOTH PLASTER AND PAINTED LIGHT GREY

THE OFFICE AND WAREHOUSE COMPONENTS ARE DESIGNED WITH BALANCED PROPORTIONS

4. BUILDING SIGNAGE

TENANT SIGNAGE PLACED ON THE NORTH AND SOUTH FACADE. THE SIGNAGE PROPORTION WAS CONSIDERED IN RELATION TO THE BUILDING ENVELOPE - REFER TO SHEET 3000

5. MATERIALITY

HIGH-QUALITY, LOW-MAINTENANCE MATERIALS THAT SUPPORT THE ARCHITECTURAL EXPRESSION WILL BE USED

6. COLORS & TEXTURES

A RANGE OF LIGHT GREY PAINTS AND BLACK SHEETING WILL BE APPLIED TO CREATE A UNIFIED INDUSTRIAL THEME

7.ROOFING

A MINIMUM PITCHED WAREHOUSE STRUCTURES
ARE INCORPORATED WITH A VISIBLE PITCH ROOF WITH METAL PROFILED SHEEDING AT 3 DEGREES. THE ROOF FORMS PART OF THE BUILDING ENVELOPE AND WAS CONSIDERED AS AN INTEGRAL AESTHETIC COMPONENT OF THE BUILDING

8.BOUNDARY WALLS

PERIMETER BOUNDARIES NOT FACING THE STREET DOES NOT EXCEED 3000MM IN HEIGHT AND ARE COMPRISED OF:

- VISUALLY PERMEABLE BETAFENCE USED FOR THE EAST,WEST AND NORTH BOUNDARY

9.MECHANICAL EQUIPMENT

MECHANICAL EQUIPMENT AND PLANT ,DUCTS, PUMPS, ETC, ARE DESIGNED INTO THE BUILDINGS AND /OR ADEQUATELY ENCLOSED OR SCREENED OFF FROM VIEW FROM ADJOINING STREETS

C:\Users\Brandon\Desktop\New folder (4)\SMITH POWER WAREHOUSE ERF 10 STELLENBOSCH BRIDGE\BRANDON\SMITH POWER WAREHOUSE STELLENBOSCH BRIDGE\REVIT\SMITH POWER CENTRAL MODELLING_MBX_SMITH POWER_SCHOOL BUSINESS20 - REVIT.rvt
2024-11-04 10:31:24


9/738
4/737
5/737
6/737
7/737
15/737
RE/1465
6/737
5/736
RAILWAY
R101
FARM No. 741
Remainder ERF 1 THE BRIDGE
1/1151
ERF 10
(PORTION OF ERF 1)
RE/1460
RE/739
FARM No. 1515
Administrative District of Stellenbosch
(Public Road)
1515
Remainder ERF 1 THE BRIDGE
PORTION 25 FARM KOOPMANS No. 52
RE/742
FARM KLAPMUTS RIVER No. 742
RE/24/32
26/32
7/744
PORTION 7 FARM WELTEVREDEN No. 744
PORTION 17 FARM WELTEVREDEN No. 744
Klapmuts Allotment Area
ROAD 13,00m
BRIGHT STREET
GENERAL PLAN No. 1007/1999
744/9
744/8
744/7
744/6
744/5
744/4
744/3
744/2
744/1
744/10
744/11
744/12
744/13
744/14
744/15
744/16
744/17
744/18
744/19
744/20
744/21
744/22
744/23
744/24
744/25
744/26
744/27
744/28
744/29
744/30
744/31
744/32
744/33
744/34
744/35
744/36
744/37
744/38
744/39
744/40
744/41
744/42
744/43
744/44
744/45
744/46
744/47
744/48
744/49
744/50
744/51
744/52
744/53
744/54
744/55
744/56
744/57
744/58
744/59
744/60
744/61
744/62
744/63
744/64
744/65
744/66
744/67
744/68
744/69
744/70
744/71
744/72
744/73
744/74
744/75
744/76
744/77
744/78
744/79
744/80
744/81
744/82
744/83
744/84
744/85
744/86
744/87
744/88
744/89
744/90
744/91
744/92
744/93
744/94
744/95
744/96
744/97
744/98
744/99
744/100
744/101
744/102
744/103
744/104
744/105
744/106
744/107
744/108
744/109
744/110
744/111
744/112
744/113
744/114
744/115
744/116
744/117
744/118
744/119
744/120
744/121
744/122
744/123
744/124
744/125
744/126
744/127
744/128
744/129
744/130
744/131
744/132
744/133
744/134
744/135
744/136
744/137
744/138
744/139
744/140
744/141
744/142
744/143
744/144
744/145
744/146
744/147
744/148
744/149
744/150
744/151
744/152
744/153
744/154
744/155
744/156
744/157
744/158
744/159
744/160
744/161
744/162
744/163
744/164
744/165
744/166
744/167
744/168
744/169
744/170
744/171
744/172
744/173
744/174
744/175
744/176
744/177
744/178
744/179
744/180
744/181
744/182
744/183
744/184
744/185
744/186
744/187
744/188
744/189
744/190
744/191
744/192
744/193
744/194
744/195
744/196
744/197
744/198
744/199
744/200
744/201
744/202
744/203
744/204
744/205
744/206
744/207
744/208
744/209
744/210
744/211
744/212
744/213
744/214
744/215
744/216
744/217
744/218
744/219
744/220
744/221
744/222
744/223
744/224
744/225
744/226
744/227
744/228
744/229
744/230
744/231
744/232
744/233
744/234
744/235
744/236
744/237
744/238
744/239
744/240
744/241
744/242
744/243
744/244
744/245
744/246
744/247
744/248
744/249
744/250
744/251
744/252
744/253
744/254
744/255
744/256
744/257
744/258
744/259
744/260
744/261
744/262
744/263
744/264
744/265
744/266
744/267
744/268
744/269
744/270
744/271
744/272
744/273
744/274
744/275
744/276
744/277
744/278
744/279
744/280
744/281
744/282
744/283
744/284
744/285
744/286
744/287
744/288
744/289
744/290
744/291
744/292
744/293
744/294
744/295
744/296
744/297
744/298
744/299
744/300
744/301
744/302
744/303
744/304
744/305
744/306
744/307
744/308
744/309
744/310
744/311
744/312
744/313
744/314
744/315
744/316
744/317
744/318
744/319
744/320
744/321
744/322
744/323
744/324
744/325
744/326
744/327
744/328
744/329
744/330
744/331
744/332
744/333
744/334
744/335
744/336
744/337
744/338
744/339
744/340
744/341
744/342
744/343
744/344
744/345
744/346
744/347
744/348
744/349
744/350
744/351
744/352
744/353
744/354
744/355
744/356
744/357
744/358
744/359
744/360
744/361
744/362
744/363
744/364
744/365
744/366
744/367
744/368
744/369
744/370
744/371
744/372
744/373
744/374
744/375
744/376
744/377
744/378
744/379
744/380
744/381
744/382
744/383
744/384
744/385
744/386
744/387
744/388
744/389
744/390
744/391
744/392
744/393
744/394
744/395
744/396
744/397
744/398
744/399
744/400
744/401
744/402
744/403
744/404
744/405
744/406
744/407
744/408
744/409
744/410
744/411
744/412
744/413
744/414
744/415
744/416
744/417
744/418
744/419
744/420
744/421
744/422
744/423
744/424
744/425
744/426
744/427
744/428
744/429
744/430
744/431
744/432
744/433
744/434
744/435
744/436
744/437
744/438
744/439
744/440
744/441
744/442
744/443
744/444
744/445
744/446
744/447
744/448
744/449
744/450
744/451
744/452
744/453
744/454
744/455
744/456
744/457
744/458
744/459
744/460
744/461
744/462
744/463
744/464
744/465
744/466
744/467
744/468
744/469
744/470
744/471
744/472
744/473
744/474
744/475
744/476
744/477
744/478
744/479
744/480
744/481
744/482
744/483
744/484
744/485
744/486
744/487
744/488
744/489
744/490
744/491
744/492
744/493
744/494
744/495
744/496
744/497
744/498
744/499
744/500
744/501
744/502
744/503
744/504
744/505
744/506
744/507
744/508
744/509
744/510
744/511
744/512
744/513
744/514
744/515
744/516
744/517
744/518
744/519
744/520
744/521
744/522
744/523
744/524
744/525
744/526
744/527
744/528
744/529
744/530
744/531
744/532
744/533
744/534
744/535
744/536
744/537
744/538
744/539
744/540
744/541
744/542
744/543
744/544
744/545
744/546
744/547
744/548
744/549
744/550
744/551
744/552
744/553
744/554
744/555
744/556
744/557
744/558
744/559
744/560
744/561
744/562
744/563
744/564
744/565
744/566
744/567
744/568
744/569
744/570
744/571
744/572
744/573
744/574
744/575
744/576
744/577
744/578
744/579
744/580
744/581
744/582
744/583
744/584
744/585
744/586
744/587
744/588
744/589
744/590
744/591
744/592
744/593
744/594
744/595
744/596
744/597
744/598
744/599
744/600
744/601
744/602
744/603
744/604
744/605
744/606
744/607
744/608
744/609
744/610
744/611
744/612
744/613
744/614
744/615
744/616
744/617
744/618
744/619
744/620
744/621
744/622
744/623
744/624
744/625
744/626
744/627
744/628
744/629
744/630
744/631
744/632
744/633
744/634
744/635
744/636
744/637
744/638
744/639
744/640
744/641
744/642
744/643
744/644
744/645
744/646
744/647
744/648
744/649
744/650
744/651
744/652
744/653
744/654
744/655
744/656
744/657
744/658
744/659
744/660
744/661
744/662
744/663
744/664
744/665
744/666
744/667
744/668
744/669
744/670
744/671
744/672
744/673
744/674
744/675
744/676
744/677
744/678
744/679
744/680
744/681
744/682
744/683
744/684
744/685
744/686
744/687
744/688
744/689
744/690
744/691
744/692
744/693
744/694
744/695
744/696
744/697
744/698
744/699
744/700
744/701
744/702
744/703
744/704
744/705
744/706
744/707
744/708
744/709
744/710
744/711
744/712
744/713
744/714
744/715
744/716
744/717
744/718
744/719
744/720
744/721
744/722
744/723
744/724
744/725
744/726
744/727
744/728
744/729
744/730
744/731
744/732
744/733
744/734
744/735
744/736
744/737
744/738
744/739
744/740
744/741
744/742
744/743
744/744
744/745
744/746
744/747
744/748
744/749
744/750
744/751
744/752
744/753
744/754
744/755
744/756
744/757
744/758
744/759
744/760
744/761
744/762
744/763
744/764
744/765
744/766
744/767
744/768
744/769
744/770
744/771
744/772
744/773
744/774
744/775
744/776
744/777
744/778
744/779
744/780
744/781
744/782
744/783
744/784
744/785
744/786
744/787
744/788
744/789
744/790
744/791
744/792
744/793
744/794
744/795
744/796
744/797
744/798
744/799
744/800
744/801
744/802
744/803
744/804
744/805
744/806
744/807
744/808
744/809
744/810
744/811
744/812
744/813
744/814
744/815
744/816
744/817
744/818
744/819
744/820
744/821
744/822
744/823
744/824
744/825
744/826
744/827
744/828
744/829
744/830
744/831
744/832
744/833
744/834
744/835
744/836
744/837
744/838
744/839
744/840
744/841
744/842
744/843
744/844
744/845
744/846
744/847
744/848
744/849
744/850
744/851
744/852
744/853
744/854
744/855
744/856
744/857
744/858
744/859
744/860
744/861
744/862
744/863
744/864
744/865
744/866
744/867
744/868
744/869
744/870
744/871
744/872
744/873
744/874
744/875
744/876
744/877
744/878
744/879
744/880
744/881
744/882
744/883
744/884
744/885
744/886
744/887
744/888
744/889
744/890
744/891
744/892
744/893
744/894
744/895
744/896
744/897
744/898
744/899
744/900
744/901
744/902
744/903
744/904
744/905
744/906
744/907
744/908
744/909
744/910
744/911
744/912
744/913
744/914
744/915
744/916
744/917
744/918
744/919
744/920
744/921
744/922
744/923
744/924
744/925
744/926
744/927
744/928
744/929
744/930
744/931
744/932
744/933
744/934
744/935
744/936
744/937
744/938
744/939
744/940
744/941
744/942
744/943
744/944
744/945
744/946
744/947
744/948
744/949
744/950
744/951
744/952
744/953
744/954
744/955
744/956
744/957
744/958
744/959
744/960
744/961
744/962
744/963
744/964
744/965
744/966
744/967
744/968
744/969
744/970
744/971
744/972
744/973
744/974
744/975
744/976
744/977
744/978
744/979
744/980
744/981
744/982
744/983
744/984
744/985
744/986
744/987
744/988
744/989
744/990
744/991
744/992
744/993
744/994
744/995
744/996
744/997
744/998
744/999
744/1000
744/1001
744/1002
744/1003
744/1004
744/1005
744/1006
744/1007
744/1008
744/1009
744/1010
744/1011
744/1012
744/1013
744/1014
744/1015
744/1016
744/1017
744/1018
744/1019
744/1020
744/1021
744/1022
744/1023
744/1024
744/1025
744/1026
744/1027
744/1028
744/1029
744/1030
744/1031
744/1032
744/1033
744/1034
744/1035
744/1036
744/1037
744/1038
744/1039
744/1040
744/1041
744/1042
744/1043
744/1044
744/1045
744/1046
744/1047
744/1048
744/1049
744/1050
744/1051
744/1052
744/1053
744/1054
744/1055
744/1056
744/1057
744/1058
744/1059
744/1060
744/1061
744/1062
744/1063
744/1064
744/1065
744/1066
744/1067
744/1068
744/1069
744/1070
744/1071
744/1072
744/1073
744/1074
744/1075
744/1076
744/1077
744/1078
744/1079
744/1080
744/1081
744/1082
744/1083
744/1084
744/1085
744/1086
744/1087
744/1088
744/1089
744/1090
744/1091
744/1092
744/1093
744/1094
744/1095
744/1096
744/1097
744/1098
744/1099
744/1100
744/1101
744/1102
744/1103
744/1104
744/1105
744/1106
744/1107
744/1108
744/1109
744/1110
744/1111
744/1112
744/1113
744/1114
744/1115
744/1116
744/1117
744/1118
744/1119
744/1120
744/1121
744/1122
744/1123
744/1124
744/1125
744/1126
744/1127
744/1128
744/1129
744/1130
744/1131
744/1132
744/1133
744/1134
744/1135
744/1136
744/1137
744/1138
744/1139
744/1140
744/1141
744/1142
744/1143
744/1144
744/1145
744/1146
744/1147
744/1148
744/1149
744/1150
744/1151
744/1152
744/1153
744/1154
744/1155
744/1156
744/1157
744/1158
744/1159
744/1160
744/1161
744/1162
744/1163
744/1164
744/1165
744/1166
744/1167
744/1168
744/1169
744/1170
744/1171
744/1172
744/1173
744/1174
744/1175
744/1176
744/1177
744/1178
744/1179
744/1180
744/1181
744/1182
744/1183
744/1184
744/1185
744/1186
744/1187
744/1188
744/1189
744/1190
744/1191
744/1192
744/1193
744/1194
744/1195
744/1196
744/1197
744/1198
744/1199
744/1200
744/1201
744/1202
744/1203
744/1204
744/1205
744/1206
744/1207
744/1208
744/1209
744/1210
744/1211
744/1212
744/1213
744/1214
744/1215
744/1216
744/1217
744/1218
744/1219
744/1220
744/1221
744/1222
744/1223
744/1224
744/1225
744/1226
744/1227
744/1228
744/1229
744/1230
744/1231
744/1232
744/1233
744/1234
744/1235
744/1236
744/1237
744/1238
744/1239
744/1240
744/1241
744/1242
744/1243
744/1244
744/1245
744/1246
744/1247
744/1248
744/1249
744/1250
744/1251
744/1252
744/1253
744/1254
744/1255
744/1256
744/1257
744/1258
744/1259
744/1260
744/1261
744/1262
744/1263
744/1264
744/1265
744/1266
744/1267
744/1268
744/1269
744/1270
744/1271
744/1272
744/1273
744/1274
744/1275
744/1276
744/1277
744/1278
744/1279
744/1280
744/1281
744/1282
744/1283
744/1284
744/1285
744/1286
744/1287
744/1288
744/1289
744/1290
744/1291
744/1292
744/1293
744/1294
744/1295
744/1296
744/1297
744/1298
744/1299
744/1300
744/1301
744/1302
744/1303
744/1304
744/1305
744/1306
744/1307
744/1308
744/1309
744/1310
744/1311
744/1312
744/1313
744/1314
744/1315
744/1316
744/1317
744/1318
744/1319
744/1320
744/1321
744/1322
744/1323
744/1324
744/1325
744/1326
744/1327
744/1328
744/1329
744/1330
744/1331
744/1332
744/1333
744/1334
744/1335
744/1336
744/1337
744/1338
744/1339
744/1340
744/1341
744/1342
744/1343
744/1344
744/1345
744/1346
744/1347
744/1348
744/1349
744/1350
744/1351
744/1352
744/1353
744/1354
744/1355
744/1356
744/1357
744/1358
744/1359
744/1360
744/1361
744/1362
744/1363
744/1364
744/1365
744/1366
744/1367
744/1368
744/1369
744/1370
744/1371
744/1372
744/1373
744/1374
744/1375
744/1376
744/1377
744/1378
744/1379
744/1380
744/1381
744/1382
744/1383
744/1384
744/1385
744/1386
744/1387
744/1388
744/1389
744/1390
744/1391
744/1392
744/1393
744/1394
744/1395
744/1396
744/1397
744/1398
744/1399
744/1400
744/1401
744/1402
744/1403
744/1404
744/1405
744/1406
744/1407
744/1408
744/1409
744/1410
744/1411
744/1412
744/1413
744/1414
744/1415
744/1416
744/1417
744/1418
744/1419
744/1420
744/1421
744/1422
744/1423
744/1424
744/1425
744/1426
744/1427
744/1428
744/1429
744/1430
744/1431
744/1432
744/1433
744/1434
744/1435
744/1436
744/1437
744/1438
744/1439
744/1440
744/1441
744/1442
744/1443
744/1444
744/1445
744/1446
744/1447
744/1448
744/1449
744/1450
744/1451
744/1452
744/1453
744/1454
744/1455
744/1456
744/1457
744/1458
744/1459
744/1460
744/1461
744/1462
744/1463
744/1464
744/1465
744/1466
744/1467
744/1468
744/1469
744/1470
744/1471
744/1472
744/1473
744/1474
744/1475
744/1476
744/1477
744/1478
744/1479
744/1480
744/1481
744/1482
744/1483
744/1484
744/1485
744/1486
744/1487
744/1488
744/1489
744/1490
744/1491
744/1492
744/1493
744/1494
744/1495
744/1496
744/1497
744/1498
744/1499
744/1500
744/1501
744/1502
744/1503
744/1504
744/1505
744/1506
744/1507
744/1508
744/1509
744/1510
744/1511
744/1512
744/1513
744/1514
744/1515
744/1516
744/1517
744/1518
744/1519
744/1520
744/1521
744/1522
744/1523
744/1524
744/1525
744/1526
744/1527
744/1528
744/1529
744/1530
744/1531
744/1532
744/1533
744/1534
744/1535
744/1536
744/1537
744/1538
744/1539
744/1540
744/1541
744/1542
744/1543
744/1544
744/1545
744/1546
744/1547
744/1548
744/1549
744/1550
744/1551
744/1552
744/1553
744/1554
744/1555
744/1556
744/1557
744/1558
744/1559
744/1560
744/1561
744/1562
744/1563
744/1564
744/1565
744/1566
744/1567
744/1568
744/1569
744/1570
744/1571
744/1572
744/1573
744/1574
744/1575
744/1576
744/1577
744/1578
744/1579
744/1580
744/1581
744/1582
744/1583
744/1584
744/1585
744/1586
744/1587
744/1588
744/1589
744/1590
744/1591
744/1592
744/1593
744/1594
744/1595
744/1596
744/1597
744/1598
744/1599
744/1600
744/1601
744/1602
744/1603
744/1604
744/1605
744/1606
744/1607
744/1608
744/1609
744/1610
744/1611
744/1612
744/1613
744/1614
744/1615
744/1616
744/1617
744/1618
744/1619
744/1620
744/1621
744/1622
744/1623
744/1624
744/1625
744/1626
744/1627
744/1628
744/1629
744/1630
744/1631
744/1632
744/1633
744/1634
744/1635
744/1636
744/1637
744/1638
744/1639
744/1640
744/1641
744/1642
744/1643
744/1644
744/1645
744/1646
744/1647
744/1648
744/1649
744/1650
744/1651
744/1652
744/1653
744/1654
744/1655
744/1656
744/1657
744/1658
744/1659
744/1660
744/1661
744/1662
744/1663
744/1664
744/1665
744/1666
744/1667
744/1668
744/1669
744/1670
744/1671
744/1672
744/1673
744/1674
744/1675
744/1676
744/1677
744/1678
744/1679
744/1680
744/1681
744/1682
744/1683
744/1684
744/1685
744/1686
744/1687
744/1688
744/1689
744/1690
744/1691
744/1692
744/1693
744/1694
744/1695
744/1696
744/1697
744/1698
744/1699
744/1700
744/1701
744/1702
744/1703
744/1704
744/1705
744/1706
744/1707
744/1708
744/1709
744/1710
744/1711
744/1712
744/1713
744/1714
744/1715
744/1716
744/1717
744/1718
744/1719
744/1720
744/1721
744/1722
744/1723
744/1724
744/1725
744/1726
744/1727
744/1728
744/1729
744/1730
744/1731
744/1732
744/1733
744/1734
744/1735
744/1736
744/1737
744/1738
744/1739
744/1740
744/1741
744/1742
744/1743
744/1744
744/1745
744/1746
744/1747
744/1748
744/1749
744/1750
744/1751
744/1752
744/1753
744/1754
744/1755
744/1756
744/1757
744/1758
744/1759
744/1760
744/1761
744/1762
744/1763
744/1764
744/1765
744/1766
744/1767
744/1768
744/1769
744/1770
744/1771
744/1772
744/1773
744/1774
744/1775
744/1776
744/1777
744/1778
744/1779
744/1780
744/1781
744/1782
744/1783
744/1784
744/1785
744/1786
744/1787
744/1788
744/1789
744/1790
744/1791
744/1792
744/1793
744/1794
744/1795
744/1796
744/1797
744/1798
744/1799
744/1800
744/1801
744/1802
744/1803
744/1804
744/1805
744/1806
744/1807
744/1808
744/1809
744/1810
744/1811
744/1812
744/1813
744/1814
744/1815
744/1816
744/1817
744/1818
744/1819
744/1820
744/1821
744/1822
744/1823
744/1824
744/1825
744/1826
744/1827
744/1828
744/1829
744/1830
744/1831
744/1832
744/1833
744/1834
744/1835
744/1836
744/1837
744/1838
744/1839
744/1840
744/1841
744/1842
744/1843
744/1844
744/1845
744/1846
744/1847
744/1848
744/1849
744/1850
744/1851
744/1852
744/1853
744/1854
744/1855
744/1856
744/1857
744/1858
744/1859
744/1860
744/1861
744/1862
744/1863
744/1864
744/1865
744/1866
744/1867
744/1868
744/1869
744/1870
744/1871
744/1872
744/1873
744/1874
744/1875
744/1876
744/1877
744/1878
744/1879
744/1880
744/1881
744/1882
744/1883
744/1884
744/1885
744/1886
744/1887
744/1888
744/1889
744/1890
744/1891
744/1892
744/1893
744/1894
744/1895
744/1896
744/1897
744/1898
744/1899
744/1900
744/1901
744/1902
744/1903
744/1904
744/1905
744/1906
744/1907
744/1908
744/1909
744/1910
744/1911
744/1912
744/1913
744/1914
744/1915
744/1916
744/1917
744/1918
744/1919
744/1920
744/1921
744/1922
744/1923
744/1924
744/1925
744/1926
744/1927
744/1928
744/1929
744/1930
744/1931
744/1932
744/1933
744/1934
744/1935
744/1936
744/1937
744/1938
744/1939
744/1940
744/1941
744/1942
744/1943
744/1944
744/1945
744/1946
744/1947
744/1948
744/1949
744/1950
744/1951
744/1952
744/1953
744/1954
744/1955
744/1956
744/1957
744/1958
744/1959
744/1960
744/1961
744/1962
744/1963
744/1964
744/1965
744/1966
744/1967
744/1968
744/1969
744/1970
744/1971
744/1972
744/1973
744/1974
744/1975
744/1976
744/1977
744/1978
744/1979
744/1980
744/1981
744/1982
744/1983
744/1984
744/1985
744/1986
744/1987
744/1988
744/1989
744/1990
744/1991
744/1992
744/1993
744/1994
744/1995
744/1996
744/1997
744/1998
744/1999
744/2000
744/2001
744/2002
744/2003
744/2004
744/2005
744/2006
744/2007
744/2008
744/2009
744/2010
744/2011
744/2012
744/2013
744/2014
744/2015
744/2016
744/2017
744/2018
744/2019
744/2020
744/2021
744/2022
744/2023
744/2024
744/2025
744/2026
744/2027
744/2028
744/2029
744/2030
744/2031
744/2032
744/2033
744/2034
744/2035
744/2036
744/2037
744/2038
744/2039
744/2040
744/2041
744/2042
744/2043
744/2044
744/2045
744/2046
744/2047
744/2048
744/2049
744/2050
744/2051
744/2052
744/2053
744/2054
744/2055
744/2056
744/2057
744/2058
744/2059
744/2060
744/2061
744/2062
744/2063
744/2064
744/2065
744/2066
744/2067
744/2068
744/2069
744/2070
744/2071
744/2072
744/2073
744/2074
744/2075
744/2076
744/2077
744/2078
744/2079
744/2080
744/2081
744/2082
744/2083
744/2084
744/2085
744/2086
744/2087
744/2088
744/2089
744/2090
744/2091
744/2092
744/2093
744/2094
744/2095
744/2096
744/2097
744/2098
744/2099
744/2100
744/2101
744/2102
744/2103
744/2104
744/2105
744/2106
744/2107
744/2108
744/2109
744/2110
744/2111
744/2112
744/2113
744/2114
744/2115
744/2116
744/2117
744/2118
744/2119
744/2120
744/2121
744/2122
744/2123
744/2124
744/2125
744/2126
744/2127
744/2128
744/2129
744/2130
744/2131
744/2132
744/2133
744/2134
744/2135
744/2136
744/2137
744/2138
744/2139
744/2140
744/2141
744/2142
744/2143
744/2144
744/2145
744/2146
744/2147
744/2148
744/2149
744/2150
744/2151
744/2152
744/2153
744/2154
744/2155
744/2156
744/2157
744/2158
744/2159
744/2160
744/2161
744/2162
744/2163
744/2164
744/2165
744/2166
744/2167
744/2168
744/2169
744/2170
744/2171
744/2172
744/2173
744/2174
744/2175
744/2176
744/2177
744/2178
744/2179
744/2180
744/2181
744/2182
744/2183
744/2184
744/2185
744/2186
744/2187
744/2188
744/2189
744/2190
744/2191
744/2192
744/2193
744/2194
744/2195
744/2196
744/2197
744/2198
744/2199
744/2200
744/2201
744/2202
744/2203
744/2204
744/2205
744/2206
744/2207
744/2208
744/2209
744/2210
744/2211
744/2212
744/2213
744/2214
744/2215
744/2216
744/2217
744/2218
744/2219
744/2220
744/2221
744/2222
744/2223
744/2224
744/2225
744/2226
744/2227
744/2228
744/2229
744/2230
744/2231
744/2232
744/2233
744/2234
744/2235
744/2236
744/2237
744/2238
744/2239
744/2240
744/2241
744/2242
744/2243
744/2244
744/2245
744/2246
744/2247
744/2248
744/2249
744/2250
744/2251
744/2252
744/2253
744/2254
744/2255
744/2256
744/2257
744/2258
744/2259
744/2260
744/2261
744/2262
744/2263
744/2264
744/2265
744/2266
744/2267
744/2268
744/2269
744/2270
744/2271
744/2272
744/2273
744/2274
744/2275
744/2276
744/2277
744/2278
744/2279
744/2280
744/2281
744/2282
744/2283
744/2284
744/2285
744/2286
744/2287
744/2288
744/2289
744/2290
744/2291
744/2292
744/2293
744/2294
744/2295
744/2296
744/2297
744/2298
744/2299
744/2300
744/2301
744/2302
744/2303
744/2304
744/2305
744/2306
744/2307
744/2308
744/2309
744/2310
744/2311
744/2312
744/2313
744/2314
744/2315
744/2316
744/2317
744/2318
744/2319
744/2320
744/2321
744/2322
744/2323
744/2324
744/2325
744/2326
744/2327
744/2328
744/2329
744/2330
744/2331
744/2332
744/2333
744/2334
744/2335
744/2336
744/2337
744/2338
744/2339
744/2340
744/2341
744/2342
744/2343
744/2344
744/2345
744/2346
744/2347
744/2348
744/2349
744/2350
744/2351
744/2352
744/2353
744/2354
744/2355
744/2356
744/2357
744/2358
744/2359
744/2360
744/2361
744/2362
744/2363
744/2364
744/2365
744/2366
744/2367
744/2368
744/2369
744/2370
744/2371
744/2372
744/2373
744/2374
744/2375
744/2376
744/2377
744/2378
744/2379
744/2380
744/2381
744/2382
744/2383
744/2384
744/2385
744/2386
744/2387
744/2388
744/2389
744/2390
744/2391
744/2392
744/2393
744/2394
744/2395
744/2396
744/2397
744/2398
744/2399
744/2400
744/2401
744/2402
744/2403
744/2404
744/2405
744/2406
744/2407
744/2408
744/2409
744/2410
744/2411
744/2412
744/2413
744/2414
744/2415
744/2416
744/2417
744/2418
744/2419
744/2420
744/2421
744/2422
744/2423
744/2424
744/2425
744/2426
744/2427
744/2428
744/2429
744/2430
744/2431
744/2432
744/2433
744/2434
744/2435
744/2436
744/2437
744/2438
744/2439
744/2440
744/2441
744/2442
744/2443
744/2444
744/2445
744/2446
744/2447
744/2448
744/2449
744/2450
744/2451
744/2452
744/2453
744/2454
744/2455
744/2456
744/2457
744/2458
744/2459
744/2460
744/2461
744/2462
744/2463
744/2464
744/2465
744/2466
744/2467
744/2468
744/2469
744/2470
744/2471
744/2472
744/2473
744/2474
744/2475
744/2476
744/2477
744/2478
744/2479
744/2480
744/2481
744/2482
744/2483
744/2484
744/2485
744/2486
744/2487
744/2488
744/2489
744/2490
744/2491
744/2492
744/2493
744/2494
744/2495
744/2496
744/2497
744/2498
744/2499
744/2500
744/2501
744/2502
744/2503
744/2504
744/2505
744/2506
744/2507
744/2508
744/2509
744/2510
744/2511
744/2512
744/2513
744/2514
744/2515
744/2516
744/2517
744/2518
744/2519
744/2520
744/2521
744/2522
744/2523
744/2524
744/2525
744/2526
744/2527
744/2528
744/2529
744/2530
744/2531
744/2532
744/2533
744/2534
744/2535
744/2536
744/2537
744/2538
744/2539
744/2540
744/2541
744/2542
744/2543
744/2544
744/2545
744/2546
744/2547
744/2548
744/2549
744/2550
744/2551
744/2552
744/2553
744/2554
744/2555
744/2556
744/2557
744/2558
744/2559
744/2560
744/2561
744/2562
744/2563
744/2564
744/2565
744/2566
744/2567
744/2568
744/2569
744/2570
744/2571
744/2572
744/2573
744/2574
744/2575
744/2576
744/2577
744/2578
744/2579
744/2580
744/2581
744/2582
744/2583
744/2584
744/2585
744/2586
744/2587
744/2588
744/2589
744/2590
744/2591
744/2592
744/2593
744/2594
744/2595
744/2596
744/2597
744/2598
744/2599
744/2600
744/2601
744/2602
744/2603
744/2604
744/2605
744/2606
744/2607
744/2608
744/2609
744/2610
744/2611
744/2612
744/2613
744/2614
744/2615
744/2616
744/2617
744/2618
744/2619
744/2620
744/2621
744/2622
744/2623
744/2624
744/2625
744/2626
744/2627
744/2628
744/2629
744/2630
744/2631
744/2632
744/2633
744/2634
744/2635
744/2636
744/2637
744/2638
744/2639
744/2640
744/2641
744/2642
744/2643
744/2644
744/2645
744/2646
744/2647
744/2648
744/2649
744/2650
744/2651
744/2652
744/2653
744/2654
744/2655
744/2656
744/2657
744/2658
744/2659
744/2660
744/2661
744/2662
744/2663
744/2664
744/2665
744/2666
744/2667
744/2668
744/2669
744/2670
744/2671
744/2672
744/2673
744/2674
744/2675
744/2676
744/2677
744/2678
744/2679
744/2680
744/2681
744/2682
744/2683
744/2684
744/2685
744/2686
744/2687
744/2688
744/2689
744/2690
744/2691
744/2692
744/2693
744/2694
744/2695
744/2696
744/2697
744/2698
744/2699
744/2700
744/2701
744/2702
744/2703
744/2704
744/2705
744/2706
744/2707
744/2708
744/2709
744/2710
744/2711
744/2712
744/2713
744/2714
744/2715
744/2716
744/2717
744/2718
744/2719
744/2720
744/2721
744/2722
744/2723
744/2724
744/2725
744/2726
744/2727
744/2728
744/2729
744/2730
744/2731
744/2732
744/2733
744/2734
744/2735
744/2736
744/2737
744/2738
744/2739
744/2740
744/2741
744/2742
744/2743
744/2744
744/2745
744/2746
744/2747
744/2748
744/2749
744/2750
744/2751
744/2752
744/2753
744/2754
744/2755
744/2756
744/2757
744/2758
744/2759
744/2760
744/2761
744/2762
744/2763
744/2764
744/2765
744/2766
744/2767
744/2768
744/2769
744/2770
744/2771
744/2772
744/2773
744/2774
744/2775
744/2776
744/2777
744/2778
744/2779
744/2780
744/2781
744/2782
744/2783
744/2784
744/2785
744/2786
744/2787
744/2788
744/2789
744/2790
744/2791
744/2792
744/2793
744/2794
744/2795
744/2796
744/2797
744/2798
744/2799
744/2800
744/2801
744/2802
744/2803
744/2804
744/2805
744/2806
744/2807
744/2808
744/2809
744/2810
744/2811
744/2812
744/2813
744/2814
744/2815
744/2816
744/2817
744/2818
744/2819
744/2820
744/2821
744/2822
744/2823
744/2824
744/2825
744/2826
744/2827
744/2828
744/2829
744/2830
744/2831
744/2832
744/2833
744/2834
744/2835
744/2836
744/2837
744/2838
744/2839
744/2840
744/2841
744/2842
744/2843
744/2844
744/2845
744/2846
744/2847
744/2848
744/2849
744/2850
744/2851
744/2852
744/2853
744/2854
744/2855
744/2856
744/2857
744/2858
744/2859
744/2860
744/2861
744/2862
744/2863
744/2864
744/2865
744/2866
744/2867
744/2868
744/2869
744/2870
744/2871
744/2872
744/2873
744/2874
744/2875
744/2876
744/2877
744/2878
744/2879
744/2880
744/2881
744/2882
744/2883
744/2884
744/2885
744/2886
744/2887
744/2888
744/2889
744/2890
744/2891
744/2892
744/2893
744/2894
744/2895
744/2896
744/2897
744/2898
744/2899
744/2900
744/2901
744/2902
744/2903
744/2904
744/2905
744/2906
744/2907
744/2908
744/2909
744/2910
744/2911
744/2912
744/2913
744/2914
744/2915
744/2916
744/2917
744/2918
744/2919
744/2920
744/2921
744/2922
744/2923
744/2924
744/2925
744/2926
744/2927
744/2928
744/2929
744/2930
744/2931
744/2932
744/2933
744/2934
744/2935
744/2936
744/2937
744/2938
744/2939
744/2940
744/2941
744/2942
744/2943
744/2944
744/2945
744/2946
744/2947
744/2948
744/2949
744/2950
744/2951
744/2952
744/2953
744/2954
744/2955
744/2956
744/2957
744/2958
744/2959
744/2960
744/2961
744/2962
744/2963
744/2964
744/2965
744/2966
744/2967
744/2968
744/2969
744/2970
744/2971
744/2972
744/2973
744/2974
744/2975
744/2976
744/2977
744/2978
744/2979
744/2980
744/2981
744/2982
744/2983
744/2984
744/2985
744/2986
744/2987
744/2988
744/2989
744/2990
744/2991
744/2992
744/2993
744/2994
744/2995
744/2996
744/2997
744/2998
744/2999
744/3000
744/3001
744/3002
744/3003
744/3004
744/3005
744/3006
744/3007
744/3008
744/3009
744/3010
744/3011
744/3012
744/3013
744/3014
744/3015
744/3016
744/3017
744/3018
744/3019
744/3020
744/3021
744/3022
744/3023
744/3024
744/3025
744/3026
744/3027
744/3028
744/3029
744/3030
744/3031
744/3032
744/3033
744/3034
744/3035
744/3036
744/3037
744/3038
744/3039
744/3040
744/3041
744/3042
744/3043
744/3044
744/3045
744/3046
744/3047
744/3048
744/3049
744/3050
744/3051
744/3052
744/3053
744/3054



PRECINCT PLAN
SCALE: 1 : 1000

DEVELOPMENT DATA: ERF 10

ZONING:	INDUSTRIAL ZONING
BUILDING CLASSIFICATION:	J2

-measures to inside of external walls
-Excludes Toilets,Service ducts,Store rooms
-Internal parking, Loading bays
-Measure stairways once

DEVELOPMENT DATA: COUNCIL GLA

ERF SITE AREA:	15 932m²

GROUND FLOOR

OFFICE GF:	595.24 m²
SERVER ROOM:	26.25 m²
AUDITORIUM:	138.03 m²
WAREHOUSE:	4922.28 m²
ELECTRICAL ROOM:	20.30 m²
BATTERY CHARGE:	31.79 m²
ICV:	7.73 m²
RECEPTION 2:	26.80 m²
PAINT:	246.90 m²
EXTERIOR WORKSHOP:	86.85 m²
WASH BAY:	58.18 m²
PUMP ROOM:	30.25 m²
REFUSE:	41.94 m²
GAURD HOUSE:	13.48 m²

FIRST FLOOR

EXTERNAL ENTERTAINMENT AREA:	55.78 m²
OFFICE FF:	414.26 m²

TOTAL COUNCIL AREA	6716.04 SQM
TOTAL OFFICE	1091.53 SQM
PARKING REQUIRED:	67
PARKING PROVIDED:	79

DEVELOPMENT DATA: SAPOA GLA

ERF SITE AREA:	15 932m²

GROUND FLOOR

OFFICE GF:	595.24 m²
SERVER ROOM:	26.25 m²
OFFICE GF WC:	29.33 m²
DISABLED WC:	6.25 m²
STORAGE:	2.71 m²
STORAGE 3:	5.95 m²
AUDITORIUM:	138.03 m²
WAREHOUSE WC:	56.63 m²
WAREHOUSE:	4922.28 m²
ELECTRICAL ROOM:	20.30 m²
BATTERY CHARGE:	31.79 m²
ICV:	7.73 m²
RECEPTION 2:	26.80 m²
PAINT:	246.90 m²
EXTERIOR WORKSHOP:	86.85 m²
WASH BAY:	58.18 m²
PUMP ROOM:	30.25 m²
REFUSE:	41.94 m²
GAURD HOUSE:	13.48 m²
DUCT 1:	9.91 m²
DUCT 1:	5.91 m²

FIRST FLOOR

EXTERNAL ENTERTAINMENT AREA:	55.78 m²
OFFICE FF:	414.26 m²
STORAGE 4:	10.52 m²
OFFICE FF WC:	53.68 m²
STORAGE 2:	6.14 m²
DUCT 3:	4.53 m²

TOTAL SAPOA GLA	6896 m²
FAR:	0.5
COVERAGE:	0.51

LEGEND

- PROPOSED 16M ACCESS SERVITUDE.
- PROPOSED 10M MUNICIPAL SEWER SERVITUDE.
- PROPOSED 3,5M MUNICIPAL WATER SERVITUDE.
- PROPOSED 5M PRIVATE SERVICES SERVITUDE.
- BULK WATER.
- BULK STORMWATER
- SEWER

STELLENBOSCH MUNICIPALITY
THIS SITE DEVELOPMENT PLAN IS APPROVED IN TERMS OF SECTION 60 OF THE STELLENBOSCH MUNICIPAL LAND USE PLANNING BY-LAW (~~2015~~), 2023 SUBJECT TO THE CONDITIONS AS PER APPENDIX.
MUNICIPAL MANAGER — DATE 4/3/2025

mbk Argitekte

General Notes:
1. All work is to be done in accordance with the National building Regulations.
2. All materials and workmanship are to comply with the relevant S.A.B.S. codes and or the specified International codes where applicable in the - Architectural specifications. Where relevant South African National Standards, British Standards, BS codes of practice, or Agrément Certificates applicable to the design exists, the recommendations and requirements of such documents to is to considered a minimum standard for the works.
3. The contractor shall in all aspects of the works comply with the provisions of the Occupational Health and Safety Act, 1993 (Act No 85 of 1993) and any regulations promulgated in terms of that Act or the Factories Machinery and Building Work Act of 1941.
4. The contractor shall set up, operate, control and maintain a quality assurance and quality control system, in accordance with SANS 2001/ISO 9001, whereby he is directed to the satisfaction of the Architect, that all materials and workmanship, whether their own or that of the sub-contractors, comply with the requirements of the Specification. Should the Contractor or any of his sub-contractors be certified to the SANS 9000 family of standards then, monitor these works accordingly.
5. This drawing must be read in conjunction with all the relevant drawings, schedules and specifications from MBK and all other consultants related to the project.
6. All portions of the works related to any service or consultant 's information is to be done in accordance with the National Building Regulations.
7. This drawing is not to be scaled. Figured dimensions to be used. All dimensions are in millimeters unless otherwise stated.
8. All dimensions and levels must be checked on site by the contractor before putting work in hand.
9. All work to be executed by competent persons qualified for the specific trade.
10. This drawings is copyright reserved and remains the property of Meester Bowers Kompanje (Pty) Ltd

REV	DATE	INITIAL	DESCRIPTION
A	29.04.24	T MS	STELLENBOSCH PRE-DDP SUB

THE BRIDGE
STELLENBOSCH

Certification that this drawing has been reviewed by the relevant Professions employed by the Developer and complies with the Approved Development Guidelines.

Lorna Donovan
Development Manager
Date: 28/11/2024

OL
OSMOND LANGE ARCHITECTS + PLANNERS (Pty) Ltd

Certification that this drawing complies with the requirements of the 2023 (Rev 1) Stellenbosch Bridge Light Industrial Precinct Manual

Graham Wilson
SACAP Reg. No. 8717
Date 21/11/2024

CLIENT

ARCHITECT

CLIENT
STELLENBOSCH BRIDGE PROPERTIES (PTY) LTD

Drawing No:
Portion 4-01-2025
Pages 2 - 5

Project Address
THE BRIDGE, ERF 10 (PORTION OF ERF 1)
Town/City
THE BRIDGE
Drawing Name
PRECINCT PLAN

SMITH POWER

stage	drawing series	revision
05	9001	A

C:\Users\Work\Desktop\Revit files - MBK\SMITH POWER WAREHOUSE STELLENBOSCH BROOKSMITH POWER WAREHOUSE STELLENBOSCH BROOKSMITH POWER COUNCIL SUBMISSION - REV 1.rvt
20241104 10:31:26



SOUTH VIEW



NORTH EAST VIEW

NORTH ELEVATION

ROOF SHEETING SPEC:

YOUNGMAN SPRINGLOK 700 CONCEALED FIX ROOF SHEETING AND ACCESSORIES
(includes loading canopies)

The roof sheeting shall be double-interlocking concealed fix Youngman Roofing Springlok 700 Concealed Fix profile roll-formed in continuous lengths and cut to length by a pneumatic cut-off process from certified AZ150 0.55mm COLORBOND® MATT steel "NIGHT SKY". The profile shall be roll-formed with three ribs at centres not exceeding 333mm and a cover width not exceeding 700mm. When interlocked, the minimum sheet depth shall be 45mm. Each trough shall incorporate two stiffener ribs. The Springlok 700 sheets shall be fixed to every purlin by means of patented, directional, AZ150 Zincalume® coated clips having spring steel flanges which will securely hold the sheets in position and lock into the centre rib, with the following clip fixed over the top of the male rib to accommodate the next roof sheet.
These clips will be fixed to purlins using 5 number 25mm wafer head Class 111 self-drilling screws (into roll formed tipped channels).

Main Roof Colour:
Sheeting Colour : NIGHT SKY
Loading Canopies:
Sheeting Colour : NIGHT SKY

ALL FIXTURES TO ROOF TO FOLLOW SUPPLIER GUIDE LINES WITH REGARDS TO METHOD OF FIXING

VERTICAL CLADDING

WIDEBEK SHEETING AND ACCESSORIES

Side Cladding to be the "Widek" profile roll-formed in continuous lengths and cut to length by a pneumatic cut-off process from certified AZ150 0.47mm **COLORBOND® MATT steel** "NIGHT SKY"/"Hidden MATT" with colour to the Broad flute (BFO). The profile shall be roll-formed with five Trapezoidal ribs at centres not exceeding 210mm and a cover width not exceeding 730mm. When lapped, the minimum sheet depth shall be 39mm. Fixed by means of Hex Head screws 35mm long for steel girts when sheets are Broad flute Out (BFO) and may incorporate 19mm diameter bonded washers.
NB. All fasteners to be either Class 111 rated according to manufacturer's recommendation.

ROOF INSULATION:
Except external canopies
50mm "Rockwise" white metalised foil facing down

CONCEALED FIX FLASHING
The paint finish shall be a top coat BlueScope Steel COLORBOND(TM) MATT steel Super Polyester of at least 25 microns and a hull coat BlueScope Steel Clean COLORBOND(TM) steel "Shadow Grey" to the reverse side **(Colour to be NIGHT SKY to match sheeting)**
0.55MM THICK)
Prior to flashings being fixed, all troughs at the apex shall be stop-ended to the full depth of the sheet in order to prevent any penetration of wind driven water. The trough shall be lapped at the eaves end to form a drip. Flashing flanges should be sheared using the appropriate broad flute metal closure and poly-closure where necessary. Care shall be taken to ensure that no sheeting or flashings will be cut with an abrasive disc/ angle grinder on roof surface in order to prevent the creation of a burn along cut edge and rivvtref (steel spanner) from penetrating colour coated sheets.

WARRANTY: 20 YEAR WARRANTIES
BlueScope Steel to issue a project specific product warranty for the use of Clean COLORBOND® steel. Warranty applications are to be submitted to BlueScope Steel prior to commencement of the project for sign off by the roofing contractor.

ERECTION
Every precaution shall be taken to prevent damage to roof sheets during all stages of construction. Dunk boards should be used when necessary to protect the sheeting from damage. Sheeting which has become deformed or damaged in any way shall be replaced.

SAFETY
The contractor shall exercise special care when handling long length sheeting, particularly in windy conditions. Should work be interrupted for any reason, all loose sheeting and incomplete sections must be adequately secured against possible movement by wind and gravity.

HANDLING AND STORAGE
The contractor shall ensure that all materials used on site for cladding, etc are transported, handled and stored in accordance with the manufacturer's recommendations. Material damaged shall be rejected and replaced with undamaged material at the contractor's expense. Repair of damaged material will not generally be permitted.
Racks are to include for preventing damage and protecting sheets through all stages of construction.
INSPECTION PRIOR TO INSTALLATION OR ERECTION
Before commencing installation, the contractor shall verify that the following items have been checked and accepted:
a. The entire structure or the portion thereof
To be sheeted has been correctly aligned, levelled and plumbed.
b. Purlins and sheeting rails are at the correct spacing and are within the specified tolerances.
c. The corners of the roof are square and the wall framework is perpendicular or as specified.
d. No protrusions such as bolt heads, splice plates, clevis, etc. appear on the face of the framework.
e. All members to which roofing and cladding are to be fixed in aesthetically sensitive areas are true and square.
f. Paint and any other materials that may be incompatible with the sheeting, have been painted over or so dealt with that direct contact with the sheeting is avoided.
g. The contact faces between the purlins or the girts and the cladding are in the same plane. Should the alignment be inadequate, The contractor shall request instructions from the engineer before proceeding

GENERAL NOTE:
ALL FLOOR CONSTRUCTION
TO ENG SPECIFICATION

GENERAL NOTE:
ALL SUPPORT OVER OPENINGS CONSTRUCTION
TO ENG SPECIFICATION

GENERAL NOTE:
ALL ROOF CONSTRUCTION
TO ENG SPECIFICATION

GENERAL NOTE:
ALL GLAZING CONSTRUCTION
TO BE ACCORDING TO PART N OF
THE SANS 10400

GENERAL NOTE:
ALL WALL CONSTRUCTION
TO ENG SPECIFICATION

GENERAL NOTE:
ALL STEEL FRAME CONSTRUCTION
TO ENG SPECIFICATION

GENERAL NOTE:
ALL COLUMN CONSTRUCTION
TO ENG SPECIFICATION

GENERAL NOTE:
ALL STAIR CONSTRUCTION
TO ENG SPECIFICATION



ROOF PLAN
SCALE: 1 : 200

STELLENBOSCH MUNICIPALITY
THIS SITE DEVELOPMENT PLAN IS APPROVED IN TERMS OF SECTION 60 OF THE STELLENBOSCH MUNICIPAL LAND USE PLANNING BY-LAW (2015), 2023
SUBJECT TO THE CONDITIONS AS PER APPENDIX.
11/3/2025
MUNICIPAL MANAGER — DATE

mbx
Argitekte

General Notes:
1. All work is to be done in accordance with the National building Regulations.
2. All materials and workmanship are to comply with the relevant S.A.B.S. codes and or the specified international codes where applicable to the - Architectural specifications. Where relevant South African National Standards, British Standards, ISO codes of practice, or Agrément Certificates applicable to the design details, the recommendations and requirements of such documents to be considered a minimum standard for the works.
3. The contractor shall in all respects of the works comply with the provisions of the Occupational Health and Safety Act, 1993 (Act No 85 of 1993) and any regulations promulgated in terms of that Act or the Factories Machinery and Building Works Act of 1941.
4. The contractor shall set up, document and maintain a quality assurance and quality control system, in accordance with SANS 9001/ISO 9001, able to be checked to the satisfaction of the Architect, that all materials and workmanship, whatever their sources, meet the requirements of the Specification, Should the Contractor or any of his sub-contractors be certified to the SANS 9000 family of standards then mention these works accordingly.
5. This drawing must be read in conjunction with all the relevant drawings, schedules and specifications from M&E and all other consultants related to the project.
6. All portions of the works related to any service or consultant 's intervention is to be done in accordance with the National Building Regulations.
7. This drawing is not to be scaled, figured dimensions to be used. All dimensions are in millimeters unless otherwise stated.
8. All dimensions and levels must be checked on site by the contractor before putting work in hand.
9. All work to be executed by competent persons qualified for the specific trade.
10. This drawings is copyright reserved and remains the property of Minette Bouwer Kompanie (Pty) Ltd

REV	DATE	DRAWN	ISSUED PURPOSE
A	2024-10-14	TVH	COUNCIL SUBMISSION

THE BRIDGE
STELLENBOSCH

Certification that this drawing has been reviewed by the relevant Professionals employed by the Developer and complies with the Approved Development Guidelines.

Lorhe Steenkamp
Development Manager

Date: 28/11/2024

OSHONO LANGE ARCHITECTS + PLANNERS (Pty) Ltd

Certification that this drawing complies with the requirements of the 2023 (Rev 1) Stellenbosch Bridge Light Industrial Precinct Manual

Graham Wilson
SACAP Reg. No. 3717

Date 21/11/2024

CLIENT

ARCHITECT

CLIENT
STELLENBOSCH BRIDGE PROPERTIES (PTY) LTD

Drawing No:

Portion 4-01-2025

Pages 3 - 5

Project Address

THE BRIDGE, ERF 10 (PORTION OF ERF 1)

Town/City

THE BRIDGE

Drawing Name

ROOF PLAN

SMITH POWER

stage	drawing series	revision
05	0001	A

C:\Users\tvanwyk\Desktop\Archive\SMITH POWER WAREHOUSE STELLENBOSCH_BRIDGE\REVIT\MODELS\SMITH POWER WAREHOUSE STELLENBOSCH_BRIDGE_CENTRAL_MODEL_tvanwyk.rvt
2024/11/04 15:31:28



GROUND FLOOR SPACE DIAGRAM PLAN

SCALE: 1 : 200



L05 FIRST FLOOR PLAN

SCALE: 1 : 200

AREA SCHEDULE (SAPOA GLA)	
Name	Area
AUDITORIUM	758.05 m²
BATTERY CHARGE	51.79 m²
DISABLED	6.25 m²
DUCT 1	9.91 m²
DUCT 2	9.91 m²
DUCT 3	4.53 m²
ELECTRICAL ROOM	20.50 m²
EXT ENTERTAINMENT AREA	56.78 m²
EXTERIOR WORKSHOP	86.83 m²
GAUTO HOUSE	13.48 m²
IZV	8.06 m²
OFFICE FF	414.26 m²
OFFICE FF WC	32.68 m²
OFFICE GF	595.24 m²
OFFICE GF WC	29.55 m²
PAINT	246.90 m²
PUMP ROOM	50.25 m²
RECEPTION 2	26.80 m²
REFUSE	41.94 m²
SERVER ROOM	26.52 m²
STORAGE	3.71 m²
STORAGE 2	6.14 m²
STORAGE 3	5.93 m²
STORAGE 4	10.03 m²
WAREHOUSE	4922.29 m²
WAREHOUSE WC	56.63 m²
WASH BAY	58.18 m²
Grand total: 27	6866.99 m²

mbk
Architekte

General Notes:
1. All work is to be done in accordance with the National Building Regulations.
2. All materials and workmanship are to comply with the relevant SA.B.S. codes and or the specified International codes where applicable in the - Architectural specifications. Where relevant South African National Standards, British Standards, BS codes of practice, or Agrément Certificates applicable to the design exists, the recommendations and requirements of such documents to be considered a minimum standard for the works.
3. The contractor shall in all aspects of the works comply with the provisions of the Occupational Health and Safety Act, 1993 (Act No 85 of 1993) and any regulations promulgated in terms of that Act or the Factories Machinery and Building Works Act of 1941.
4. The contractor shall set up, document and maintain a quality assurance and quality control system, in accordance with SANS 9001/ISO 9001, able to be checked to the satisfaction of the Architect, that all materials and workmanship, whatever their sources, meet the requirements of the Specification. Should the Contractor or any of his sub-contractors be certified to the SANS 9000 Series standards this must be stated clearly and accordingly.
5. This drawing is to be used in conjunction with all the relevant architectural and specifications from MEP, and all other consultants related to the project.
6. All portions of the works related to any service or consultant 's information is to be done in accordance with the National Building Regulations.
7. This drawing is not to be scaled, Figured dimensions to be used. All dimensions are in millimeters unless otherwise stated.
8. All dimensions and levels must be checked on site by the contractor before putting work in hand.
9. All work to be executed by competent persons qualified for the specific trade.
10. This drawings is copyright reserved and remains the property of Meiring Steyn Kompanje (Pty) Ltd

REV	DATE	DRAWN	DESCRIPTION
A	2024.10.21	FVN	CLIENTS SUBMISSION

THE BRIDGE
DEVELOPMENT

Certification that this drawing has been reviewed by the relevant Professionals employed by the Developer and complies with the Approved Development Guidelines.

Lemos Dawson
Development Manager

Date: 29/11/2024

OSMOND LANGE ARCHITECTS + PLANNERS (Pty) Ltd

Certification that this drawing complies with the requirements of the 2023 (Rev 1) Stellenbosch Bridge Light Industrial Precinct Manual

Graham Wilson
SACAP Reg. No. 3717

Date 21/11/2024

CLIENT

ARCHITECT

STELLENBOSCH MUNICIPALITY

THIS SITE DEVELOPMENT PLAN IS APPROVED IN TERMS OF SECTION 60 OF THE STELLENBOSCH MUNICIPAL LAND USE PLANNING BY-LAW (~~2015~~), 2023 SUBJECT TO THE CONDITIONS AS PER APPENDIX.

MUNICIPAL MANAGER

11/3/2025
DATE

CLIENT
STELLENBOSCH BRIDGE PROPERTIES (PTY) LTD

Drawing No:

Portion 4-01-2025

Pages 4 - 5

Project Address
THE BRIDGE, ERF 18 (PORTION OF ERF 1)

Town/City
THE BRIDGE

Drawing Name
GENERAL ARRANGEMENT FUNCTIONS PLAN

SMITH POWER

page	drawing suffix	revision
05	1000	A

C:\USERS\DAWSON\DESKTOP\BRIDGE - GAUTENG\POWER WAREHOUSE STELLENBOSCH BRIDGE\24\04\WITH POWER WAREHOUSE STELLENBOSCH BRIDGE\REVIT\ARCHITECTURAL\POWER_WAREHOUSE_CENTRAL_DAWSON.RVT 24/11/2024 10:31:34

STELLENBOSCH MUNICIPALITY

THIS SITE DEVELOPMENT PLAN IS APPROVED IN TERMS OF SECTION 60 OF THE STELLENBOSCH MUNICIPAL LAND USE PLANNING BY-LAW (~~2015~~), 2027 SUBJECT TO THE CONDITIONS AS PER APPENDIX.

MUNICIPAL MANAGER

11/3/2025
DATE

THE BRIDGE
STELLENBOSCH

Certification that this drawing has been reviewed by the relevant Professionals employed by the Developer and complies with the Approved Development Guidelines.

Lenre Dannpaa
Development Manager

Date: 28/11/2024

mbx
Argitekte

General Notes:
1. All work is to be done in accordance with: the National building Regulations,
2. All materials and workmanship are to comply with the relevant S.A.B.S. codes and or the specified international codes where applicable in the Architectural specifications. Where relevant South African National Standards, British Standards, BS codes of practice, or Agrément Certificates applicable to the design exists, the recommendations and requirements of such documents to be considered a minimum standard for the works.
3. The contractor shall in all aspects of the works comply with the provisions of the Occupational Health and Safety Act, 1993 (Act No 85 of 1993) and any regulations promulgated in terms of that Act or the Factories Machinery and Building Works Act of 1941.
4. The contractor shall set up, document and maintain a quality assurance and quality control system. In accordance with SANS 9001:ISO 9001, able to be checked to the satisfaction of the Architect, that all materials and workmanship, whether their sources, meet the requirements of the Specification. Should the Contractor or any of his sub-contractors be certified to the SANS 9000 family of standards then monitor these works accordingly.
5. This drawing must be read in conjunction with all the relevant drawings, schedules and specifications from MBX and all other consultants related to the project.
6. All portions of the works related to any service or consultant's installation is to be done in accordance with the National Building Regulations.
7. This drawing is not to be scaled. Figured dimensions to be used. All dimensions are in millimeters unless otherwise stated.
8. All dimensions and levels must be checked on site by the contractor before putting work in hand.
9. All work to be executed by competent persons qualified for the specific trade.
10. This drawings is copyright reserved and remains the property of Meester Bouers Kompanje (Pty) Ltd

REV	DATE	DRAWN	DESCRIPTION
1	2024-09-29	STT	ANOTHER STEP ADDED, F.F.O ADDED
A	2024-11-28	Fan	PLANNING SUBMISSION





FIRST FLOOR PLAN

SCALE: 1:200

GENERAL NOTE:
ALL FLOOR CONSTRUCTION
TO ENG SPECIFICATION

GENERAL NOTE:
ALL SUPPORT OVER OPENINGS CONSTRUCTION
TO ENG SPECIFICATION

GENERAL NOTE:
ALL ROOF CONSTRUCTION
TO ENG SPECIFICATION

GENERAL NOTE:
ALL GLAZING CONSTRUCTION
TO BE ACORDING TO PART N OF THE SANS 10400

GENERAL NOTE:
ALL WALL CONSTRUCTION
TO ENG SPECIFICATION

GENERAL NOTE:
ALL STEEL FRAME CONSTRUCTION
TO ENG SPECIFICATION

GENERAL NOTE:
ALL COLUMN CONSTRUCTION
TO ENG SPECIFICATION

GENERAL NOTE:
ALL STAIR CONSTRUCTION
TO ENG SPECIFICATION

AREA SCHEDULE (SAPOA GLA)

Name	Area
AUDITORIUM	138.03 m²
BATTERY CHARGE	31.79 m²
DISABLED	6.22 m²
DUCT 1	1.91 m²
DUCT 2	5.91 m²
DUCT 3	4.53 m²
ELECTRICAL ROOM	20.30 m²
EXT ENTERTAINMENT AREA	55.78 m²
EXTERIOR WORKSHOP	86.83 m²
GAURD HOUSE	13.48 m²
ICV	8.06 m²
OFFICE FF	414.26 m²
OFFICE FF WC	31.68 m²
OFFICE GF	595.24 m²
OFFICE GF WC	29.33 m²
PAINT	246.90 m²
PUMP ROOM	30.25 m²
RECEPTION 2	26.80 m²
REFUSE	41.94 m²
SERVER ROOM	26.52 m²
STORAGE	2.71 m²
STORAGE 2	9.14 m²
STORAGE 3	5.95 m²
STORAGE 4	10.52 m²
WAREHOUSE	4922.28 m²
WAREHOUSE WC	56.63 m²
WASH BAY	58.18 m²
Grand total: 27	6886.19 m²

ZONING:	INDUSTRIAL ZONING
BUILDING CLASSIFICATION:	J2

-measures to inside of external walls
-Excludes Toilets,Service ducts,Store rooms
Internal parking, Loading bays
-Measure stairways once

APEX HEIGHT:	13.644m
ALLOWED APEX HEIGHT:	16m

DEVELOPMENT DATA: COUNCIL GLA

ERF SITE AREA:	13 952m²

GROUND FLOOR

OFFICE GF:	595.24 m²
SERVER ROOM:	26.25 m²
AUDITORIUM:	138.03 m²
WAREHOUSE:	4922.28 m²
ELECTRICAL ROOM:	20.30 m²
BATTERY CHARGE:	31.79 m²
ICV:	7.78 m²
RECEPTION 2:	26.80 m²
PAINT:	246.90 m²
EXTERIOR WORKSHOP:	86.83 m²
WASH BAY:	58.18 m²
PUMP ROOM:	30.25 m²
REFUSE:	41.94 m²
GAURD HOUSE:	13.48 m²

FIRST FLOOR

EXTERNAL ENTERTAINMENT AREA:	55.78 m²
OFFICE FF:	414.25 m²

TOTAL COUNCIL AREA	6716.04 SQM
TOTAL OFFICE	1091.53 SQM
PARKING REQUIRED:	67
PARKING PROVIDED:	79

DEVELOPMENT DATA: SAPOA GLA

ERF SITE AREA:	13 952m²

GROUND FLOOR

OFFICE GF:	595.24 m²
SERVER ROOM:	26.25 m²
OFFICE GF WC:	29.33 m²
DISABLED WC:	6.25 m²
STORAGE:	2.71 m²
STORAGE 3:	5.95 m²
AUDITORIUM:	138.03 m²
WAREHOUSE WC:	56.63 m²
WAREHOUSE:	4922.28 m²
ELECTRICAL ROOM:	20.30 m²
BATTERY CHARGE:	31.79 m²
ICV:	7.78 m²
RECEPTION 2:	26.80 m²
PAINT:	246.90 m²
EXTERIOR WORKSHOP:	86.83 m²
WASH BAY:	58.18 m²
PUMP ROOM:	30.25 m²
REFUSE:	41.94 m²
GAURD HOUSE:	13.48 m²
DUCT 1:	9.91 m²
DUCT 2:	5.91 m²

FIRST FLOOR

EXTERNAL ENTERTAINMENT AREA:	55.78 m²
OFFICE FF:	414.26 m²
STORAGE 4:	10.52 m²
OFFICE FF WC:	31.68 m²
STORAGE 2:	6.14 m²
DUCT 3:	4.53 m²

TOTAL SAPOA GLA	6886 m²
FAR:	0.5
COVERAGE:	0.51

OSHOND LANGE ARCHITECTS + PLANNERS (Pty) Ltd

Certification that this drawing complies with the requirements of the 2023 (Rev 1) Stellenbosch Bridge Light Industrial Precinct Manual

Graham Wilson
SACAP Reg. No. 3717

Date 21/11/2024

CLIENT

ARCHITECT

CLIENT
STELLENBOSCH BRIDGE PROPERTIES (PTY) LTD

Drawing No:
Portion 4-01-2025
Pages 5 - 5

Project Address
THE BRIDGE, ERF 10 (PORTION OF ERF 1)
Town/City
THE BRIDGE
Drawing Name
GENERAL ARRANGEMENT PLAN

SMITH POWER

stage	drawing series	revision
05	1001	A

C:\Users\Admin\Desktop\Work\2024\SMITH POWER WAREHOUSE STELLENBOSCH BRIDGE\SMITH POWER WAREHOUSE STELLENBOSCH BRIDGE_CENTRAL_WORK\SMITH POWER DRAWING SUBMISSION_R20.rvt
20241126 13:51:41



PLANT LIST

TREES - ALL DOUBLE-STAKED (100L TO 400L SIZE) NOTE: TREES IN PARKING AREAS MINIMUM 100L SIZE

BRACHYLEANA DISCOLOR
BUDDLEJA SALIGNA
EKEBERGIA CAPENSIS
HARPEPHYLLUM CAFFRUM
PITTOSPORUM VIRIDIFLORUM
SYZYGIUM GUINEENSE
TARCHONANTHUS CAMPHORATUS

SHRUBS AND GROUNDCOVERS (3-7/M²)

ARISTEA MAJOR
AGAPANTHUS PREACOX
ARCTOTIS SP.
ASYSTASIA GANGETICA
BARLERIA REPENS
CARISSA MACROCARPA
COLEONOMA ALBUM
DIETES GRANDIFLORA
ELEGIA CAPENSIS
ELEGIA TECTORUM
FICINIA NODOSA
GAZANIA SP.
HELICHRYSUM PETIOLARE
JUNCUS KRAUSII
PELARGONIUM SP.
PLECTRANTHUS CILIATUS
POLYGALA MYRTIFOLIA
SEARSIA CRENATA
TECOMA CAPENSIS
WATSONIA SP.

SWALES AND WETLANDS (3-7/M²)

APONOGETON DISTACHYOS
BOLBOSCHOENUS MARITIMUS
BULBOSCHOENUS MARITIMUS
CAREX CLAVATA
CHASMANTHE AETHIOPICA
CYPERUS TEXTILIS
ELEGIA SP
FICINIA NODOSA
ISOLEPIS LUDWIGII
ISOLEPIS PROLIFER
JUNCUS EFFUSUS
MARICUS THUNBERGII
NYMPHAEA CAPENSIS (BLUE)
RESTIO FESTUCIFORMIS
SCHOENOPLECTUS SP
SCIRPUS NODOSUS
THAMNOCHORTUS INSIGNIS
WACHENDORFIA THYRSIFLORA
ZANTEDESCHIA AETHIOPICA

LEGEND	
	PLANTING
	LAWN
	NEW TREES
	160Ø IRRIGATION SLEEVES



TREE SURROUND DETAIL
SCALE 1:100

NOTES:

1) AN IRRIGATION SYSTEM IS TO BE INSTALLED IN ALL PLANTED AREAS. SPRAYER OVERLAP TO BE 100%. ALL TREES TO HAVE IRRIGATION AS PART OF THE OVERALL SYSTEM. ALL PIPES AND FITTINGS TO BE SABS APPROVED AND TO THE LANDSCAPE ARCHITECTS APPROVAL. ALL IRRIGATION SLEEVES ARE TO BE 110mm Ø. POSITIONED 600mm BELOW FINISHED LEVEL OF ROAD KERBING OR PAVING, AND ARE TO EXTEND 600mm BEYOND EDGE OF ROAD KERBING OR PAVING. ALL SLEEVES ARE TO RUN TO THE SIDE OF TREE OPENINGS, NOT THE CENTRE.

2) A MIN. 40mm IRRIGATION WATER CONNECTION POINT MUST BE PROVIDED NEAR THE IRRIGATION MAINLINE

3) ALL TREES TO BE STAKED USING 2x50mm DIA. TANALITH TREATED POLES DRIVEN 600mm INTO THE GROUND AND TIED BY MEANS OF TWO RUBBER HOSES AND WIRE OR COMMERCIAL TREE TIES. CARE MUST BE TAKEN NOT TO DAMAGE THE ROOT BALL OF THE TREE.



REVISIONS		
REV NO.	DESCRIPTION	TYPE OF ISSUE
00	DRAWING CREATED	FOR INFO.
01	DRAWING AMENDED	FOR INFO.
02	DRAWING AMENDED	FOR INFO.
03	DRAWING AMENDED	FOR INFO.

FOR INFORMATION

SMITH POWER

LANDSCAPE PLAN

Drawing No: 2996 - 03 - LP - REV 03

[redacted]

STELLENBOSCH
STELLENBOSCH • PNIEL • FRANSCHHOEK

MUNICIPALITY • UMASIPALA • MUNISIPALITEIT

ANNEXURE E

STELLENBOSCH MUNICIPALITY

STELLENBOSCH·PNIEL·FRANSCHHOEK

MEMORANDUM

DIREKTEUR: INFRASTRUKTUURDIENSTE
DIRECTORATE: INFRASTRUCTURE SERVICES

CIVIL ENGINEERING SERVICES

To / Aan:	**Director: Planning + Economic Development**
Att Aandag:	**Nicole Katts**
From / Van:	**Manager: Development (Infrastructure Services)**
Author / Skrywer:	**Tyrone King**
Date / Datum:	**4 November 2024**
Our Ref / Ons Verw:	**Civil LU 2774**
Town Planning Ref:	**LU/17383**
Re / Insake:	**Farm 742/5, Paarl: Application is hereby made in terms of Section 15(2)(l) of the Municipal Bylaw on Land Use Planning, 2023 for permission in terms of a condition of approval for the approval of a Site Development Plan as per Condition 3.5 of the Land Use approval granted on 25 August 2023.**

The following engineering documents were evaluated as part of this application:

- Civil engineering services report by UDS dated 10 Nov 2023
- TIS by UDS dated 10 Nov 2023

Background: This approval is solely related to Erf No 4 as pictured below and these conditions are based on +/- 6807m^2 GLA of industrial use planned to be constructed on this erf, and it's impact on the external engineering services.

In consideration of provisions related to Civil Engineering Services the application is supported subject to the following conditions:

Specific Conditions: These conditions must be complied with prior to transfer of the first property or approval of any building plans, whichever occurs first.

1. Water

1.1 The following upgrades must be installed (see **Annexure: Services**):

1.1.1 Pipeline SKW1.1: 560mm dia
1.1.2 Pipeline SKW1.2a: 560mm dia
1.1.3 Pipeline SKW 1.2b: 560mm dia
1.1.4 Pipeline SKW 1.5: 400mm dia
1.1.5 Pipeline SKW 1.21. 355mm dia
1.1.6 Pipeline SKW 1.11: 200mm dia

The cost hereof can be offset from DCs. There is already an Engineering Services Agreement in place for these items – ESA 118.

1.2 All municipal servitudes for the water lines must be registered.

1.3 A bulk water meter conforming to the specifications of the Directorate: Infrastructure Services must be installed, the municipal account for the said meter must be activated and the consumer deposit must be paid. The positing of the bulk water meter is to be agreed with this office, prior to installation, and must be indicated on the building plan for the buildings on erf 4.

2. Sewer

2.1 The following upgrades must be installed (see **Annexure: Services**):

2.1.1 The 355mm dia municipal sewer line between the site and the existing outfall sewer to the west. The cost hereof can be offset from DCs. There is already an Engineering Services Agreement in place for these items – ESA 118.

2.2 All municipal servitudes for the sewer line must be registered.

2.3 A servitude must be registered over Precint 2, to the west, as this is private property.

3. Roads

3.1 The following upgrades must be installed:

3.1.1 Upgrading of Merchant – and Pickering Street intersection: the existing intersection will be widened to improve the turning movements of larger vehicles including reconstruction of the sidewalks.

3.1.2 Upgrading of the R44 – Stellengate Boulevard and Klapmuts/Simondium Road intersection: the existing roadway will be widened to accommodate dedicated turning lanes including reconstruction of the sidewalks and relocation of the traffic signals.

3.1.3 The Klapmuts Hills Road – as a single carriageway for the first phase, as shown in yellow on **Annexure: Services** and including all associated works (stormwater etc).

The cost hereof can be offset from DCs – only the public portion/s of the roads. There is already an Engineering Services Agreement in place for these items – ESA 118.

3.2 Any conditions stated by the Provincial Roads Engineer must be complied with.

4. Stormwater

4.1 The following stormwater items must be installed:

4.1.1 Stormwater channel (overland stormwater swale +/-1.45km in length) as indicated on Plan Number UDS318A_Report Key Plan dated October 2024 by UDS **(Annexure SW)**.

The cost hereof will be for the Developer.

The swale shall be an interim measure and must be piped when the adjacent erven is developed as indicated in the engineering services report.

During this interim stage, if and when in the opinion of the Municipality, further works is required on the stormwater system, to make it more formalized and to ensure adequate drainage and minimize erosion, such works as identified by the Municipality, must be carried out by the Developer within the timeframes required by the Municipality.

4.2 Various regional stormwater detention ponds have been identified in the Stormwater Management Report (March 2023). These are not yet triggered at this stage but will be further assessed as the Stellenbosch Bridge development rolls out.

5. Solid Waste

5.1 The refuse embayment must be completed to allow easy access for municipal refuse vehicles to the refuse room on collection days and to prevent obstruction to traffic flows.



6. Servitudes

6.1 All servitudes as indicated on **Annexure: Services**, must be registered. Should the need for additional servitudes be discovered after the date of this Memo, it will also be a requirement. It is the Developer's responsibility to ensure that all servitudes are identified upfront, to avoid delays at clearance stage.

7. Installation of Engineering Services

7.1 Over and above the bulk and external upgrades identified above, each newly created erf (or each building where subdivision is not applicable) must also be fully serviced ito water- and sewer connections, stormwater drainage and roads/access points. All internal and link engineering services for the development must be installed by the developer at his cost.

7.2 Detail engineering drawings must be submitted for approval prior to the commencement of construction. The engineering drawings approval letter issued by the Municipality will constitute the "engineering services agreement" for the provision and installation of services between the municipality and the land owner / developer, as stated in the municipality's land-use planning by-law.

8. Development Charges (DCs)

8.1 DCs are payable in accordance with the prevailing and applicable Council DCs Tariffs and DCs Policy at the time of payment prior to the transfer of the first property or approval of any building plans, whichever occurs first. The amount payable will therefore be the amount as calculated according to the approved tariff structure and according to the DCs Policy principles at the time that payment is made.

8.2 A final DC calculation will be provided prior to Building Plan approval. The details on the building plans will be used for such DC calculation.

8.3 It is acknowledged that the Developer has done upgrades in lieu of DCs as part of the roll-out of this development. A DCs reconciliation must be submitted together with the building plans to determine the amount of DCs payable.

8.4 This DC reconciliation will also be required before clearance of the erf to determine if the Developer is in a "DC credit" or not, due to upgrades done in lieu of DCs or if any DCs are payable to the municipality before clearance.

8.5 Where DCs are identified above as a potential funding source for bulk services, the Developer must enter into a DCs Agreement with the Municipality to install or upgrade bulk municipal services, to be off-set against the DCs payable.

9. As - Builts

9.1 Upon completion, a complete set of as-built drawings, as well as the asset verification information (in the case of municipal services) be submitted in a format acceptable to the Municipality. These drawings must be signed by a professionally registered engineer.

General Conditions

10. The implementation of the development wrt the provision of civil engineering services, must comply with the "*General guidelines and standard practices for the provision of civil engineering services for new developments*" as published on the municipality's website and as amended from time-to-time.
11. The design of the civil engineering services for the development must comply with the "*Design Guidelines and Minimum Standards for Civil Engineering Services*" as published on the municipality's website and as amended from time-to-time.
12. The internal services are private. Therefore, all internal services will be maintained by the Developer and/or Owner's Association.
13. The Developer will be held liable for any damage to municipal infrastructure, caused as a direct result of the development of the subject property. The Developer will therefore be required to carry out the necessary rehabilitation work, at his/her cost, to the standards of the Directorate: Infrastructure Services, prior to transfer of the first property or approval of any building plans or occupation certificate, whichever occurs first.

Tyrone King Pr Tech Eng
MANAGER: DEVELOPMENT (INFRASTRUCTURE SERVICES)


LEGEND
THE BRIDGE
THE BRIDGE SERVICES SDR
MASTERPLAN
LAYOUT
1:2000
OCTOBER 2021
LDS1164_RE-PORTS
KEY PLAN


EXAMPLE OF SWALE
EXAMPLE OF SWALE
EXAMPLE OF SWALE